

Government of Nepal
Ministry of Infrastructure Development
Department of Roads
Federal Highway Monitoring & Supervision Office
ROAD DIVISION BAITADI
Office Code: 337017401

BILL OF QUANTITY

Name of Project: Road Safety Works in Anarkholi-Khodpe-Patan-Satbanjh-Jhulaghat Section(Ch:0+000 to 89+000) to Midhill Highway (NH-03)
Contract No: RDBTD/33701136/2083/84-12

S.N.	Description of Works	Unit	Quantity	Rate (NRs.)	Rate (NRs.) In Words	Amount (NRs.)
1	Provisional Sum					
1.1	Relocation of public service utilities, minor infrastructures, irrigation canals, existing electric poles, water supply, engineer's facility,etc. as directed by Engineer.	PS	1.00	20,000.00	Twenty thousand Only	20,000.00
1.2	Insurance for the (a) loss or damage to the Works, Plant, Materials, Equipment, Property and Personnel Injury or death as per SCC 19.1 [SS 100]	PS	1.00	20,000.00	Twenty thousand only	20,000.00
2	Road Safety Works					
2.1	Providing and installation of 150 mm * 150 mm* 1. 50 m long delineators, 60-80 cm high above ground level, painted black and white in 20 cm wide strips, buried or pressed into the ground and conforming to the drawings and Technical Specifications. [SS 1507]	No	250.00			
2.2	Providing and fixing of Covex mirror Heavy Duty Steel Tube internal 50 mm dia. firmly fixed to the ground by means of properly designed foundation with M 10/40 grade cement concrete 300 mm x 300 mm x 300 mm, as per drawings and Technical Specification/ DOR Publication.	No	50.00			

Government of Nepal
Ministry of Infrastructure Development
Department of Roads
Federal Highway Monitoring & Supervision Office
ROAD DIVISION BAITADI
Office Code: 337017401

BILL OF QUANTITY

Name of Project: Road Safety Works in Anarkholi-Khodpe-Patan-Satbanjh-Jhulaghat Section(Ch:0+000 to 89+000) to Midhill Highway (NH-03)
Contract No: RDBTD/33701136/2083/84-12

S.N.	Description of Works	Unit	Quantity	Rate (NRs.)	Rate (NRs.) In Words	Amount (NRs.)
2.3	Providing and fixing of Non reflective warning, mandatory sign board of size 60 cm height equilateral triangle/80 cm x 60 cm rectangular of 2 mm thick MS Sheet with back support frame fixed on heavy 50 mm tube or Channel section of 75 mm X 40 mm firmly fixed to the ground by means of properly designed foundation with M 10/40 grade cement concrete 300 mm x 300 mm x 300 mm, 1 as per drawings and Technical Specification/ DOR Publication.[SS1501]	No	60.00			
2.4	Painting Two Coats of on Steel Surfaces, Providing and applying two coats of ready mix paint of approved brand on steel surface after through cleaning of surface to give an even shade as per Drawing and Technical Specifications.[SS1501]	Sqm	85.93			
2.5	Painting Two Coats of Enamel Paint, Providing and Painting on Old Delineator Posts as per instruction of Site Engineer.[S1501]	Sqm	310.56			
2.6	Painting Two Coats of Enamel Paint, Painting & Lettering on Old Kilometer Posts as per instruction of Site Engineer.	No	18.00			

Government of Nepal
Ministry of Infrastructure Development
Department of Roads
Federal Highway Monitoring & Supervision Office
ROAD DIVISION BAITADI
Office Code: 337017401

BILL OF QUANTITY

Name of Project: Road Safety Works in Anarkholi-Khodpe-Patan-Satbanjh-Jhulaghat Section(Ch:0+000 to 89+000) to Midhill Highway (NH-03)

Contract No: RDBTD/33701136/2083/84-12

S.N.	Description of Works	Unit	Quantity	Rate (NRs.)	Rate (NRs.) In Words	Amount (NRs.)
2.5	Road Marking with Hot Applied Thermoplastic Compound with Reflectorizing Glass Beads on Bituminous Surface, On smooth surface (similar to Asphalt concrete and rigid pavement), Providing and laying of hot applied thermoplastic compound at least 2 mm thick including reflectorizing glass beads as per DOR Traffic sign manual/ Specifications .The finished surface to be level, uniform and free from streaks and holes.[SS1504]	Sqm	1040.00			
Total Amount (Inc. PS), NRs.:						
Amount of PS, NRs.:						
Total Amount (Exc. PS), NRs.:						
VAT @ 13%, NRs.:						
Total Amount (Inc. PS & VAT), NRs.:						