



Government of Nepal
Ministry of Infrastructure Development
Department of Roads
Federal Highway Monitoring & Supervision Office
ROAD DIVISION BAITADI
Office Code: 337017401

BILL OF QUANTITY

Name of Project: Road Safety Works in Khodpe -Chainpur Highway, CH:0+000 to 107+000 (NH-64)

Contract No: RDBTD/33701136/2083/84-13

S.N.	Description of Works	Unit	Quantity	Rate (NRs.)	Rate (NRs.) In words	Amount (NRs.)
1	Provisional Sum					
1.1	Insurance for the (a) loss or damage to the Works, Plant, Materials, Equipment, Property and Personnel Injury or death as per SCC 19.1 [SS 100]	PS	1.00	15,000.00	Fifteen Thousand Only	15,000.00
2	Road Safety Works					
2.1	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. By Manual Means for Maintenance of Sign Posts [SS 907]	Cu.m	4.05			
2.2	Providing and laying of Plain/Reinforced Cement Concrete of grade M10/40 including necessary formworks,compaction ,curing and testing all complete as per drawing and technical Specifications.By Mannual Means for Maintenance of Sign Posts[SS 2000]	Cu.m	4.05			



Government of Nepal
Ministry of Infrastructure Development
Department of Roads
Federal Highway Monitoring & Supervision Office
ROAD DIVISION BAITADI
Office Code: 337017401

BILL OF QUANTITY

Name of Project: Road Safety Works in Khodpe -Chainpur Highway, CH:0+000 to 107+000 (NH-64)

Contract No: RDBTD/33701136/2083/84-13

S.N.	Description of Works	Unit	Quantity	Rate (NRs.)	Rate (NRs.) In words	Amount (NRs.)
2.3	Providing and fixing of Non reflective warning, mandatory sign board (80 cm x 60 cm rectangular or 60 cm height equilateral triangle) of 2 mm thick MS Sheet with back support frame fixed on heavy 50 mm tube or Channel section of 75 mm X 40 mm firmly fixed to the ground by means of properly designed foundation with M 10/40 grade cement concrete 300 mm x 300 mm x 300 mm, as per drawings and Technical Specification/ DOR Publication.	No	295.00			
2.4	Painting Two Coats on Steel Surfaces, Providing and applying two coats of ready mix paint of approved brand on steel surface after through cleaning of surface to give an even shade as per Drawing and Technical Specifications.	Sqm	148.82			
2.5	Kilometer Stone, Providing and Fixing Reinforced cement concrete M 15 grade kilometer Post including painting and printing as per Standard Drawing-2070 and Technical Specifications. position, One kilometer Post (precast)[SS 1506]	No	29.00			



Government of Nepal
Ministry of Infrastructure Development
Department of Roads
Federal Highway Monitoring & Supervision Office
ROAD DIVISION BAITADI
Office Code: 337017401

BILL OF QUANTITY

Name of Project: Road Safety Works in Khodpe -Chainpur Highway, CH:0+000 to 107+000 (NH-64)

Contract No: RDBTD/33701136/2083/84-13

S.N.	Description of Works	Unit	Quantity	Rate (NRs.)	Rate (NRs.) In words	Amount (NRs.)
2.6	Kilometer Stone, Providing and Fixing Reinforced cement concrete M 15 grade kilometer Post including painting and printing as per Standard Drawing-2070 and Technical Specifications. position, Five kilometer Post (precast)[SS 1506]	No	7.00			
Total Amount (Including PS), NRs.:						
Amount of PS, NRs.:						
Total Amount (Excluding PS), NRs.:						
VAT @ 13%, NRs.:						
Total Amount (Including PS & VAT), NRs.:						