



Government of Nepal
Ministry of Infrastructure Development
Department of Roads
Federal Road Supervision & Monitoring Office, Kathmandu
Road Division, Bharatpur
Chitwan



BILL OF QUANTITIES

Contract Identification No : RDBHT/337310113/083/84-01

Name of the Work : Reactive Maintenance Works on Mahanagar Ring Road (NH77) Chitwan

Location of the Work : Gondryang-Meghauli-Pulchok

S.N.	Description of Works	Unit	Quantity	Bidder's Rate (NRs.)	Bidder's Rate (in words)	Total (NRs.)
1	General Works					
1.1	Insurance for loss of or damage to works, plant, material, equipment, property and personnel injury or death and third party as per contract data including mobilization, demobilization expenses for manpower, equipment and performance bond commission.	LS	1			
1.2	Traffic flow management either by diversion or controlled access with the help of traffic police and /or trained personnel; by providing traffic safety and personnel safety, assurance by announcements through public media etc. and safety management with supply of retro reflective jackets, helmets etc. to contractor's and employer's staffs during working period [104]	LS	1			
2	Reactive Maintenance Works					
2.1	Providing and laying crusher Run Base on prepared surface, spreading and mixing, watering and compacting to form a layer of base course as per Drawing and Technical Specifications.(SS/SP 1204)	Cum	12			
2.2	Providing and laying slurry seal consisting of a mixture of fine aggregates, Portland cement filler, bituminous emulsion and water on a road surface including cleaning of surface, mixing of slurry seal in a suitable mobile plant, laying and compacting to provide even riding surface as per Drawing and Technical Specifications [3 mm thickness] (SS/SP 2903)	Sqm	23750			



Government of Nepal
Ministry of Infrastructure Development
Department of Roads
Federal Road Supervision & Monitoring Office, Kathmandu
Road Division, Bharatpur
Chitwan



BILL OF QUANTITIES

Contract Identification No : RDBHT/337310113/083/84-01

Name of the Work : Reactive Maintenance Works on Mahanagar Ring Road (NH77) Chitwan

Location of the Work : Gondryang-Meghauli-Pulchok

S.N.	Description of Works	Unit	Quantity	Bidder's Rate (NRs.)	Bidder's Rate (in words)	Total (NRs.)
2.3	Providing required material and repairing the pot holes with close graded Premix 20 mm including removal of failed material, trimming and finishing the surface applying tack coat on the sides and base of excavation, backfilling with hot premix carpet and compaction as per Technical Specification and instruction of the Engineer.[2903]	Sqm	1250			
Total						
VAT @ 13%						
Grand Total with VAT						

Signature of Authorised Person:

Name of Authorised Person:

Contractor's Name:

Address and Telephone No.:

Seal:

Date: