



Government of Nepal
Ministry of Infrastructure Development
Department of Roads
Federal Highway Supervision and Monitoring Office, Kathmandu
Road Division Bharatpur, Chitwan
Bill of Quantities (BOQ)



Name of the project : Structural and Road Maintenance Works Along Kaligandaki Corridor from Gaidakot (0+000) to Damaraphat (78+000) Section

Location :Kaligandaki Corridor (Nawalpur Section)

Contract no: RDBHT/33701138/083/84-06

SN	Description of Works	Unit	Quantity	Bidders Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
1.0	General Works						
1.1	Provisional sum for relocation of infrastructures, utilities & other unforeseen items of works during the execution of project	PS	1.00	100000.00	One Lakh Rupees Only	100,000.00	
1.2	Insurance of works, plants, materials and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property.	LS	1.00				
2.0	Earthworks						
2.1	Clearance of landslides in soil and ordinary rock by machine including excavation, loading and disposal of the same on the valley side or loaded to a truck upto relevant lead as per drawing / direction of Engineer. [SS 2900,900]	Cum	5280.00				
3.0	Drainage and Retaining Structure						
3.1	Earthwork in excavation of foundation of structures in all types of soil by mechanical means , including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved material as per drawing and technical specifications. [SS 907]	Cum	2376.75				



Government of Nepal
Ministry of Infrastructure Development
Department of Roads
Federal Highway Supervision and Monitoring Office, Kathmandu
Road Division Bharatpur, Chitwan
Bill of Quantities (BOQ)



विश्वविद्यालय

Name of the project : Structural and Road Maintenance Works Along Kaligandaki Corridor from Gaidakot (0+000) to Damaraphat (78+000) Section
Location :Kaligandaki Corridor (Nawalpur Section)
Contract no: RDBHT/33701138/083/84-06

SN	Description of Works	Unit	Quantity	Bidders Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
3.2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.[SS 3111]	Cum	95.47				
3.3	Providing and laying machine mixed Plain Cement Concrete of grade M15/40 in foundation including formworks all complete as per drawing and Technical Specification [SS 2000]	Cum	63.65				
3.4	Providing and laying Random Rubble Stone Masonry work in cement mortar 1:4 in structure including scaffolding, curing, preparation of mortar and providing necessary 75 mm dia polythene pipes for weep holes etc all complete as per Drawing and Technical Specifications [SS 2602/2603,2607]	Cum	1363.50				



Government of Nepal
Ministry of Infrastructure Development
Department of Roads
Federal Highway Supervision and Monitoring Office, Kathmandu
Road Division Bharatpur, Chitwan
Bill of Quantities (BOQ)



विश्वविद्यालय

Name of the project : Structural and Road Maintenance Works Along Kaligandaki Corridor from Gaidakot (0+000) to Damaraphat (78+000) Section

Location :Kaligandaki Corridor (Nawalpur Section)

Contract no: RDBHT/33701138/083/84-06

SN	Description of Works	Unit	Quantity	Bidders Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
3.5	Supplying of Machine made Heavy Coated Hexagonal Mesh type 100mm x 120 mm Gabion boxes / mattresses of with diaphragms, with Lacing wire 2.4 mm, mesh wire 3.0mm and selvaged wire 3.9mm , assembling Gabion Boxes mattresses, palcing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and providing and filling stone / boulder in gabion boxes / mattresses etc. including dressing, bedding, bonding and all transporation all complete as per specification.[SS-2402]	Cum	1686.00				
3.6	Providing, laying and fixing of Geo-textile all complete as per drawing and technical specification. [2404]	Sqm	944.00				
4.0	Pavement Maintenance						
4.1	Providing and laying 50mm thick penetration macadam over prepared Base by providing a layer of compacted crushed coarse aggregate with applications of bituminous binder and key aggregates as per Drawing and Technical Specifications. [SS 1304]	Sqm	266.20				

Name of the project : Structural and Road Maintenance Works Along Kaligandaki Corridor from Gaidakot (0+000) to Damaraphat (78+000) Section

Location :Kaligandaki Corridor (Nawalpur Section)

Contract no: RDBHT/33701138/083/84-06

SN	Description of Works	Unit	Quantity	Bidders Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
4.2	Providing required material and repair the potholes with closed graded Premix 20mm including removal of failed material, trimming and finishing the surface applying tack coat on the sides and base of excavation, backfilling with hot bituminous Material and compaction as per Technical Specification and instruction of the Engineer (SS Clause 2903).	Sqm	3096.00				
				Total Amount including PS (A)			
				PS Amount (B)		100,000.00	
				Total Amount without PS (C)=A-B			
				VAT @ 13% (D)=13% of C			
				Grand Total E=(B+C+D)			

Signature of Authorised Person:
Name of Authorised Person:
Contractor's Name:
Address and Telephone No.:
Seal:
Date: