



नेपाल सरकार  
भौतिक पूर्वाधार तथा वातावरण मन्त्रालय  
सडक विभाग  
हेभी ईक्वीपमेण्ट डिभिजन  
इटहरी, सुनसरी



ईमेल hed\_itaharid@dor.gov.np  
फोन ०२४२८०१६४

दररेट उपलब्ध गराउने सम्बन्धि सूचना

IDENTIFICATION NUMBER :- HEDITH/DP/080-081/25

(प्रकाशित मिति २०८१।०२।१४)

यस डिभिजन अन्तर्गत रहेका वर्कसपमा सेड निर्माण गर्नुपर्ने भएकोले कार्यालयमा सूचिकृत भएका सम्बन्धित निर्माण व्यवसायी र सूचिकृत नभएका सम्बन्धित निर्माण व्यवसायीहरूलाई समेत व्यवसाय दर्ता सम्बन्धि प्रमाणपत्र, कर चुक्ताको प्रमाणपत्र, प्यान भ्याट दर्ता लगायतका आवश्यक कागजात सहित सूचिकृत हुन निवेदन सहित मिति २०८१।०२।२० गते कार्यालय समय भित्र यसै पत्रसाथ सलग्न Bill of Quantity मा दररेट भरी उपलब्ध गराई दिनुहुन अनुरोध छ।

खरिद ईकाइ प्रमुख

मेकानिकल इन्जिनियर

Government of Nepal  
Ministry of Physical Infrastructure and Transport  
Department of Roads  
**Heavy Equipment Division**  
(Babari, Sunsari)  
**ABSTRACT OF COST**



**Budget head:**  
**Descriptions of works:**  
**Name of work:** Construction of Motor Garage in Heavy Equipment Division (TAHARI)  
**FY-2080/81**

S.N.	Description of Items	Unit	Quantity	Rate, NRs.		Remarks
				In Figure	In Word	
A	General					
1	Earthwork in excavation in ordinary soils including necessary hauling distance all complete as per instruction of site Engineer.	m3	8.64			
2	Providing and laying of hand pack stone soiling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per drawing and Technical Specifications [SS2602,2603,2608]	m3	0.86			
3	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per drawing and Technical Specifications . RCC Grade M 20/20 including formwork complete as per instruction of Site Engineer.	m3	1.53			
4	Providing and laying . fitting and placing HYSD reinforcement complete in foundation as per instruction of Site Engineer.	KG	111.20			
5	Supplying and fixing MS steel pipe and MS steel plate etc with two coat of anti-	KG	3,192.48			

*[Signature]*  
असिस्टन्ट इन्जिनियर

	corrosive paint. Rate shall include fabrication and fixing supplying, delivering at site, hosting and fixing position etc and including all necessary accessories as per instruction of Site Engineer.							
6	0.41 mm (Heavy class 26 gauge) Colour CGI sheet roofing with proper shape and size, all necessary nails, screws, bolts, nuts washers, J hook or L hook etc as per drawing and instruction all complete as per instruction of the Site Engineer.	m2	170.66					
7	0.26 mm colour plain sheet ridge roofing with proper shape and size, all necessary nails, screws, bolts, nuts washers, J hook or L hook etc as per drawing and instruction all complete as per instruction of the Site Engineer.	RM	25.00					
<b>Total amount</b>								
<b>VAT @ 13% OF Total Amount</b>								
<b>Grand Total including VAT amount</b>								



*(Signature)*  
 श्रीकृष्ण इन्डिया

Contractors Name :-  
 Contractors Firm Name :-  
 Signature and Stamp :-  
 Date :-