



नेपाल सरकार
भौतिक पूर्वाधार तथा यातायात मन्त्रालय
सडक विभाग
हेभी इक्वीपमेन्ट डिभिजन

प.सं.२०८०/०८१
च.नं.

नेपाल सरकार
भौतिक पूर्वाधार तथा यातायात मन्त्रालय
सडक विभाग
हेभी इक्वीपमेन्ट डिभिजन
नेपालगंज, बाँके

नेपालगंज (बाँके)

मिति:-२०८१/०२/१६

ने.सं.११४४, बछलागा ६ बुधवार

दररेट उपलब्ध गराउने सम्बन्धि सूचना

IDENTIFICATION NUMBER:- HEDNPJ/DP/080-081/01

(प्रकाशित मिति:-२०८१/०२/१६)

यस डिभिजन अन्तर्गत रहेका वर्कशपमा सेड मर्मत गर्नुपर्ने भएकोले कार्यालयमा सूचिकृत भएका सम्बन्धित निर्माण व्यवसायी र सूचिकृत नभएका सम्बन्धित निर्माण व्यवसायीहरूलाई समेत व्यवसाय दर्ता सम्बन्धि प्रमाण पत्र, कर चुक्ताको प्रमाण पत्र, पान भ्याट दर्ता लगायतका आवश्यक कागजात सहित सूचिकृत हुन निवेदन सहित मिति २०८१/०२/२२ गते कार्यालय समय भित्र यसै पत्र साथ संलग्न Bill Of Quantity मा दररेट भरी उपलब्ध गराईदिनु हुन अनुरोध छ ।

खरीद ईकाइ प्रमुख
ओम बहादुर थापा
मेकानिकल इन्जिनियर

Government of Nepal
Ministry of Physical Infrastructure and Transport
Department of Roads
HEAVY EQUIPMENT DIVISION NEPALGUNJ

BILL OF QUANTITY



Budget Head No. :
Contract ID No.:
Name of Job: Repair and maintenance of Roofing work
Location: Heavy Equipment division Nepalgunj

F/Y: 080/81

S.N.	Description of works	Unit	Quantity	Rate (NRs)	Amount (NRs)	Remarks
A General Works						
1	Insurance for the loss or damage to works, plant, materials and contractor's equipment, property including personnel injury or death. (CL 13, GCC 117)	LS	1.00			
B Site Clearance						
1	Dismantalling Work	0.00	0.00			
i)	Roofing Area	m2	234.00			
ii)	For wall	m3	9.52			
C Structure Work						
1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	m3	2.77			
2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	m3	0.59			
3	Providing and laying of PCC (Grade M 15 including form work) in foundation complete as per Drawing and Technical Specifications	m3	0.39			
4	Providing and laying Brick Masonry Work in Cement mortar (cement:sand 1:4) in Foundation/Structure complete excluding pointing, plastering etc all complete as per Drawing and Technical Specifications	m3	15.95			
5	Providing and laying of RCC (Grade M 25 including form work) in foundation complete as per Drawing and Technical Specifications	m2	1.86			
6	Providing and laying, fitting and placing HYSD bar reinforcement in foundation complete as per Drawing and Technical Specifications (SS Clause 2014)	m2	0.18			
7	Plaster work (1.4) cement sand mortar	m2	112.00			
8	One coat primer with wither coat	m2	407.20			
9	0.5 mm thick Curregated colour CGI Sheet	m2	255.00			
10	Plain Sheet colour (0.5mm thick)	rm	25.50			
Total						
VAT @13%						
Grand Total						

Shubam
मेकानिकल ईन्जिनियर