

Government of Nepal
Ministry of Physical Infrastructure and Transport
Department of Roads
BRIDGE BRANCH



BILL OF QUANTITIES


Feasibility Study, Detailed Engineering Survey, Soil Investigation, Hydrological Study and Detailed Design of the bridge(s):

S. N.	Name of Bridge	Name of Road	District
1	Mehanagad R.C. Bridge	Asigram VDC	Dadeldhura
2	Dhakani Kurmule R.C. Bridge	0	Dadeldhura
3	Khohi Khola R.C. Bridge	Asigram VDC	Dadeldhura
4	Sunkhola Road R.C. Bridge	Aalital VDC	Dadeldhura
5	Bhangredi Khola Road Bridge,	Aalital	Dadeldhura
6	Mahakali River Bridge	0	Dadeldhura
7	Mahakali River Bridge	0	Baitadi
8	Mahakali River Bridge	0	Darchula
9	Kalagad Bridge	(Baikalpik Lok Marg)	Darchula

												Contract No.		BB-159-DSD-072/73-43		
SN	Particulars	Unit	Quantity									Total quantity	Rate (excl. VAT)	Rate in words	Amount (excl. VAT)	
			Mehanagad R.C. Bridge	Dhakani Kurmule R.C. Bridge	Kholi Khola R.C. Bridge	Sunkhola Road R.C. Bridge	Bhangredi Khola Road Bridge,	Mahakali River Bridge	Mahakali River Bridge	Mahakali River Bridge	Kalagad Bridge					
	Desk study and field works															
1	Desk Study including collection of data, maps and other information; planning of the works	Job	1	1	1	1	1	1	1	1	1	9				
2	Field works including general reconnaissance, feasibility study, detailed engineering survey of the site, geological & geomorphologic study, field survey, topographic survey, site selection and environmental study, detailed hydrometric and hydrological study and preliminary soil investigation in test pits	Job	1	1	1	1	1	1	1	1	1	9				
Subtotal of desk study & field works																
	Submission of Feasibility Study Report - 3 copies	If the any of the bridge(s) is found to be unfeasible then the work(s) of that bridge(s) will be terminated at this stage and payment shall be made according to SCC Clause no. 6.4 (a) & (b) NOTE.														
3 Soil investigation																
3.1 Drilling of boreholes and carryout specified Field and Laboratory tests as per the TOR																
	Number of boreholes		3	2	2	3	3	4	4	3	2	26	-----	-----	-----	
a	Drilling 0 to 20 m in clayey,sandy soils,& gravel mixed soils (Type_1)	RM	0	0	0	0	0	0	0	0	40	40				
b	Drilling 0 to 16 m in gravel,pebbles,cobbles & boulders, soft and hard rock (Type_2)	RM	48	32	32	48	48	64	64	48	0	384				
Subtotal of drilling works, field tests and laboratory tests																

Bill of Quantities

SN	Particulars	Unit	Quantity									Total quantity	Rate (excl. VAT)	Rate in words	Amount (excl. VAT)
			Mehanagad R.C. Bridge	Dhakani Kummule R.C. Bridge	Kholi Khola R.C. Bridge	Sunkhola Road R.C. Bridge	Bhangredi Khola Road Bridge,	Mahakali River Bridge	Mahakali River Bridge	Mahakali River Bridge	Kalagad Bridge				
4	Transportation														
4.1	Transportation of personnel	job	1	1	1	1	1	1	1	1	1	9			
4.2	Transportation of equipment	job	1	1	1	1	1	1	1	1	1	9			
	Subtotal of transportation														
5	Detailed design and preparation of reports														
5.1	Detailed design works, preparation of cost estimates including bridge type selection, design of bridge, approach roads and river training works and preparation of drawing works as per TOR	job	1	1	1	1	1	1	1	1	1	9			
5.2	Submission and presentation of of the works as per TOR including 2 copies in electronic formats (CD-ROM) and (separate sets for each bridge)	job	1	1	1	1	1	1	1	1	1	9			
	Subtotal of detailed design and preparation of reports														
	Grand Total														



In words:

Signature:

Name and title:

Date:

Seal: