

Final Copy



GOVERNMENT OF NEPAL
MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT
DEPARTMENT OF ROADS
BRIDGE BRANCH

STANDARD SUPERSTRUCTURE DRAWINGS FOR ROAD BRIDGES

15.0m Simply Supported Span, Cast - in - situ,

4 webbed Reinforced Concrete Slab - Deck

SKEW ANGLE : 0° to 15°

(CARRIAGE WIDTH - 7.5m WITH BOTH SIDE FOOTPATH - 1.75m = TOTAL WIDTH - 11.0m)

REFERENCE NOTES

- All dimensions are in millimeters, unless stated otherwise.
- No dimension shall be scaled from the Drawings; only written dimensions shall be followed.
- Any doubtful Dimensions/Descriptions shall be brought to the attention of the Engineer-in-Charge for any conditions (if any) before execution of work.
- Number of reinforcement bars shall not be counted from the Drawings. Only given spacing and/or specified number of bars, shall be provided.
- All materials and workmanship shall be in accordance with these NOTES and those in the stated Drawings and shall be generally in accord with the applicable Specifications and relevant Standards/Codes of Practice specified therein and Sound Engineering Practice, in that order.

- This Bridge Superstructure is designed for One Lane of IRC Class 70R Loading, Two Lanes of IRC Class A Loading, and One Lane of IRC Class A Loading, whichever governs. In addition to a Footpath 1.5m Load corresponding to 500 kN/m² of Footpath area as per Clause 28.3 of IRC - I (2017). However, the present Footpath also has also been designed for a wheel Load of 4 Tonnes (distributed over a contact area of 300 mm dia) per axle 205.4 of IRC - I (2017), allowing 25% increase in stresses due to flexure.
- The Contractor shall be responsible for constructing and maintaining all parts of the structure in stable, accessible and serviceable condition, ensuring no part under construction is unduly stressed and unsafe.

- CONSTRUCTION SEQUENCE:** Enter Deck (i.e. the Superstructure comprising the cast in situ Reinforced Concrete deck slab) shall preferably be constructed in one operation in one day for one span. If it is not possible, then the four webs shall be cast one after the other (each up to about 150 mm below the top floor) on one day (if possible) otherwise on two successive days, one after the other with the Cross Girders, and then the cast on the next day. This entire Deck must be cast in situ on slabs in span in not more than three successive days.

CEMENT:

- A high strength Ordinary Portland Cement 53 Grade, conforming to IS: 12269 or 43 Grade conforming to IS: 8111, capable of achieving the required design concrete Strength and Durability, shall be used.
- Cement shall be obtained from approved Manufacturers only.

- Cement content in the Concrete Mix for Reinforced Concrete shall not be less than 300 kg/m³ and not more than 450 kg/m³.

COARSE AND FINE AGGREGATES:

- Maximum size of Coarse Aggregate used shall be 20mm. Fineness Modulus of Sand (Fine Aggregate) shall not be less than 2.3. Both these Aggregates shall be of Approved Quality, from Approved Sources, and of Approved Gradations, etc. conforming to IS: 383 (1970), in zones of congestion in the structural sections. If absolutely necessary, 12 mm down sized Coarse Aggregates may be used (but the Mix shall then be re-designed to suit).
- In zones of congestion in a structural section, if absolutely necessary, 12 mm down sized Coarse Aggregates may be used (but the Mix shall then be re-designed to suit).

- ADDITIONS:** To suitably improve workability and increase initial setting time of concrete and cement content, Additives conforming to IS: 9103, and ASTM C-494 Type F water-reducing, high range admixtures, shall be permitted in appropriate dosages, subject to their satisfactory proven use.

REINFORCEMENT:


- All reinforcing steel bars shall be High Yield Strength Deformed type and Thermally Mechanically Treated, having specified minimum 0.2 per cent proof stress of 500 MPa conforming to IS: 1786.
- Minimum lap-length of reinforcement bars shall be 55d where d is the dia. of the smaller bar to be lapped (unless otherwise specified).
- Not more than 50 percent of reinforcement crossing a section shall be lapped at that location.
- All laps in reinforcement shall be properly staggered and minimum distance between the laps shall be 1.3 times the lap length.
- Bending of reinforcement bars shall be as per IS: 1902.

- WATER:** Water for concrete and for its curing shall be of potable quality and presence of any salts, sugars and pollutants like chlorides, sulphates, alkalis, etc., shall be well within their limits specified in the relevant Specifications.

CONCRETE AND REINFORCING:

- WATER-CEMENT RATIO:** by weight, shall not exceed 0.45 for Reinforced concrete.
- MINIMUM CLEAR CONCRETE COVER:** to reinforcement bars shall be 40mm.
- CONTROL OF SURFACE EVAPORATION**

SURFACE EVAPORATION FROM PLASTIC CONCRETE



Use the graphical Figure below to estimate and control the loss of water through surface evaporation in the wet concrete area. One or more of the following actions shall be taken to reduce the surface evaporation rate to no more than one kilogram of water per square meter of surface area per hour.

- Construct Windbreakers to effectively reduce the wind velocity (to suit) in the area of concrete placement. The construction of windbreakers or enclosure should not proceed without approval of the Engineer with respect to their structure design relative to safety, stability, safety, and vibrations in the low work.

- Install stationary Fog Sprayers upwind of the concreting operation to effectively increase the relative humidity in the area of concrete placement.

- When necessary, effectively reduce the temperature of concrete (to suit) by cooling one or more of its components as well as lightly spray wet the slabs and the feet reinforcement, i.e., if added to the mix-water, shall be completely melted prior to using that water.

GRADES OF CONCRETE

The structural concrete involved in this Bridge Deck shall be suitably designed as High Strength Concrete Mass having 28 day minimum water Cube Crushing Strength in Compression on 150 mm Standard Cubes as follows:

For the cast in situ (i.e.) Reinforced Concrete & Reinforced Concrete Superstructure (i.e. for its Slabs/Girders, Slab and Cross-girders)	35 MPa (i.e. M-35 Grade Concrete)
For the Reinforced Concrete in: - Precast Footpath Slabs - Parapet Walls and their Bases - Road Kerbs	35 MPa (i.e. M-35 Grade Concrete)

CONSTRUCTION JOINTS:

- As far as possible the location of Construction joints shall be as shown in the Drawings, but if not shown on the Drawings but found absolutely necessary, they shall be planned in advance and the placing of concrete carried out continuously from Joint to Joint.

- A Construction Joint should not be located near the centroid level of the section as here transverse SHEAR stress is highest. The joint should be nearly perpendicular to the principal lines of tensile stress and in general be located at points of minimum stress and minimum moment, as far as possible.

- Where dowels, reinforcing bars, or other adequate ties are not shown at Construction Joints in the Drawings, they shall be formed at reasonable spacing by embedding water soaked twisted tendons while the concrete is still soft.

- These keys should be sized as may be shown in the details, or as directed by the Engineer, and these key-forming timbers shall be removed when the concrete has fully set.

- In resuming concreting work, the surface of the concrete previously placed shall first be thoroughly cleaned of dirt, slum, laitance, loose projecting aggregates and any other soft material, using stiff wire brushes, and, if deemed necessary, by the Engineer, by sand blasting.

- The concrete surface shall then be thoroughly soaked with clean water (just before further concreting) and the water, etc. at shown away, and the cleaned concrete surface paired with a thin layer of cement slurry, and only then further concrete poured.

- "Wire-mesh" and other similar items do not provide a proper construction joint, and they shall not be used.

F. COLD JOINT

- When a planned continuous placement of concrete in any structural member is interrupted or delayed, for any reason, for a period long enough to the previously partially placed concrete to take its initial set, the Engineer may decide such a joint as a Cold Joint and the Contractor shall immediately remove the previously partially placed concrete from the Forms.

- However, where feasible, the previously partially placed concrete may indeed be suitably and carefully hatched and its hooked end brought into low shear low moment zone as far as possible, and given shear key depressions after bringing it nearly perpendicular to the principal lines of tensile stress (for example brought to vertical or nearly vertical in a beam with principal bending reinforcement horizontal) and thereafter some treatment shall be given to it as to a Construction Joint and only then the concreting resumed (making sure all reinforcements are as per the approved Drawings and the Shuttering has been brought to line and plumb tightly).

G. CURING AND PROTECTION OF YOUNG CONCRETE:

- All structural concrete shall be cured for a period of time required to obtain the specified strength, but for not less than fourteen consecutive days (at night) beginning immediately after initial setting of concrete (which is when it loses its surface damp).

- Curing (Membrane-curing or Water-curing) of laid concrete shall be carried out as generally explained above.

H. Membrane-Curing the Concrete:

- Except for at Construction Joints and surfaces sealed by Forms, liquid membrane curing compound can be used for curing the concrete as follows:

- On bridge deck top surface and other exposed surfaces, liquid membrane curing compound shall be applied soon after initial setting and as the Surface Sheen has disappeared and the concrete is still slightly damp (not wet).

- On shuttered i.e. formed vertical surfaces, Forms shall be stripped as soon as practicable (generally after 24 hours of casting) and liquid membrane curing compound applied immediately against the areas that require rubbing or finishing during the curing period.

- These areas shall be kept water-tight until their finishing is completed, where after the liquid curing membrane shall be uniformly applied on them also when their surface is damp.

- White pigmented liquid membrane curing compound shall be used for all surfaces where the structure temperature during curing period is likely to reach about 35°C or more.

- For bridge decks which are to receive an asphaltic overlay, residual curing membrane (after curing) shall be removed prior to the overlaying.

- Removal methods and results should be approved by the Engineer.

- The membrane curing compound used shall be of longer lasting duration and in accordance with the requirements specified for curio membrane material, AASHTO M 145 or the equivalent IS Specification.

- The curing compound shall be applied in two applications one immediately following the other.

- The rate of each application of curing compound shall be as prescribed by the manufacturer, with a spreading rate per application of at least one liter of liquid per square meter of concrete surface.

- If the concrete has dried up or has become dry, it shall be thoroughly wetted with water and the curing compound applied just as the surface film of water disappears and the surface is damp.

- During curing operations any unsprayed surfaces shall be kept cured with watered Hessian cloth, and sprayed with the curing compound when Surface is damp (not wet).

- Any curing membrane material on Construction Joints and/or on reinforcing steel shall be completely removed before the following concrete pour.

- Hand operated spraying equipment shall be capable of applying concrete and uniform pressure to provide uniform and even distribution of the curing membrane at the sites required.

- The curing compound shall be kept thoroughly mixed at all times during usage / application.

- No traffic of any kind shall be permitted on the curing membrane until the curing period is completed, despite permitting.

I. Water-Curing the Concrete:

- All concrete surfaces, unless still sealed by unreleased Forms (which shall be kept from heating up under ambient temperature) or submerged, shall be water cured unless liquid membrane curing.

- Water curing shall begin just after initial setting of concrete (which generally occurs by about 60 minutes of placement of un-admixture concrete) and shall be continued for 50 minutes of placement of admixture concrete, and just after the surface water sheen has disappeared.

- Surfaces water-cured shall be covered with wet sand, cotton mats, or double-thickness burlap (jute/hessian) sheets.

- This Hessian material shall be placed tightly round and behind any projecting reinforcing steel in order to completely cover the fresh concrete surface.

- i.e. The Hessian material shall be completely saturated with water and kept continuously saturated throughout the curing period.

- After the initial saturation, unless water is kept running, all surfaces shall be covered with thick polythene sheeting or other approved impervious material in order to protect/dry-up of concrete surface being cure continuously.

- The sheeting shall be weighed down or secured well to prevent moisture loss but the surfaces of the concrete shall be readily available for inspection of the Engineer (or his Representative).

- The sheeting material shall be in good repair.

- Sheeting that contains holes or is otherwise damaged shall be repaired or replaced immediately.

- The Contractor shall be responsible for thoroughly inspecting and monitoring the concrete surfaces throughout the curing period to detect continuous wetting and curing.

- Additional water shall be poured on any areas where saturation is reduced.

- Inspection of curing by the Contractor shall be conducted at least TEN times per day and night for the duration of the curing period - and even more often if ordered by the Engineer.

- The Engineer shall be advised of the curing inspection schedule and he (or his Representative) may accompany the worker to verify the acceptability of curing.

K. "COLD-WEATHER" CURING:

- When concrete is placed and the air temperature is expected to drop below 5°C during the curing period, the Contractor shall provide suitable measures such as straw, additional burlap or other suitable insulating materials and/or housing and artificial hot-curing to maintain the concrete temperature between 10°C and 32°C as measured on the surface of the concrete.

- The surface of the concrete shall be kept moist and warm by the use of an approved water-retaining material, such as wet burlap/hessian.

- The medium barrier shall be maintained in airtight surface contact with the concrete during the entire curing period.

- After the completion of the curing during the entire required curing period, the Contractor shall stop the curing and remove the protection in such a manner that rapid cooling of the concrete will not occur.

- When concrete is placed in "cold-rooms" and subsequently flooded with ground water, the above curing conditions may be waived, provided the surface of the water is not permitted to freeze.

N. "CONCRETING" IN "ADVERSE WEATHER" CONDITIONS:

1. "Concreting" in "Cold Weather":

- Concrete that freezes soon after placing, gains rather low strength and some permanent damage is liable to occur. Therefore, such concrete shall be removed and replaced immediately.

- Planning for Protection of Fresh concrete during placement, and until it has attained the minimum properties required for the environment and the loading to which it will be subjected, shall be done with in advance of concreting and approved by the Engineer.

- Appropriate equipment shall be made available in time for heating the concrete materials, for constructing enclosures and for maintaining favorable temperatures even after the concrete is placed.

- Concrete shall never be placed cold and cold steel.

- When the temperatures of these items is below 5°C, the Contractor shall use means to raise their temperatures to above 10°C.

- When faced with prolonged cold temperatures, at aggregates, or mixing water, or both, shall be heated to about 25°C to 32°C.

- At temperature at least 10°C above freezing, it is seldom necessary to heat the Aggregates.

- At temperatures below or at freezing, often only the Fine Aggregate is heated to produce concrete of the required temperature, provided the Coarse Aggregate is free of frozen lumps and the Temperature of Water for the Mix is at least 10°C.

- If aggregate temperatures are above freezing, the desired concrete temperature usually can be obtained by heating only the mixing water.

CONTINUE

GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS BRIDGE DIVISION	
STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGES	
Need Concrete Width: 1.5m with 3 Footpaths each 1.5m wide	Overall Deck Width: 11.00 m
Effective Span/Support Span (Center to center of Bearings): 10.0 m and Reinforced Concrete Deck	
Use LIVE LOAD IRC Class of 70R or 1 of 2 Lanes of Class A, whichever governs, and Footpath Loading	
Sp. No. 17 of 4-Webbed RC-Slab Deck 15.0 m-Span	
Sp. TITLE: REFERENCE NOTES (1 Sheet) of Sheet 12	
Reviewed by: Anil Kumar Virmia (Engineer, DOE)	Forwarded by: Jyoti Malla (SDE, DOE)
Recommended by: Dipak Shrestha (SDE, DOE)	Approved by: Ajay Jung Thapa (SDE, DOE)
Date: June 2021	Page: 00

- | | | |
|--|--|---------------------|
| Prepared by:
Jyoti Varna
(DO, DoR) | Prepared by:
Jyoti Varna
(DO, DoR) | Date:
June, 2021 |
| Approved by:
Jyoti Varna
(DO, DoR) | Approved by:
Jyoti Varna
(DO, DoR) | Revisions:
00 |

LIST OF DRAWINGS	
DRAWING NO.	DRAWING TITLE
1 of 7 4-Wheelor RC Slab Deck 15.0m x 55.5m Span	REFERENCE NOTES (2 Sheets) Sheet 1/2
2 of 7 4-Wheelor RC Slab Deck 15.0m x 55.5m Span	REFERENCE NOTES (2 Sheets) Sheet 2/2
3 of 7 4-Wheelor RC Slab Deck 15.0m x 55.5m Span	SUPERSTRUCTURE OUTLINE & DIMENSIONS
4 of 7 4-Wheelor RC Slab Deck 15.0m x 55.5m Span	REINFORCEMENT DETAILS OF DECK SLAB, REINFORCEMENT WITH SLAB, ROAD KERB & PARAPET POST
5 of 7 4-Wheelor RC Slab Deck 15.0m x 55.5m Span	REINFORCEMENT DETAILS OF LONGITUDINAL GIRDER
6 of 7 4-Wheelor RC Slab Deck 15.0m x 55.5m Span	REINFORCEMENT DETAILS OF CROSS GIRDER & MISCELLANEOUS DETAILS
7 of 7 4-Wheelor RC Slab Deck 15.0m x 55.5m Span	BAR BENDING SCHEDULE

GOVERNMENT OF NEPAL
MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT
DEPARTMENT OF ROADS
BRIDGE BRANCH


STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGE

Road Carriageway Width: 7.50m with 2 Footpaths each 1.30m wide	Overall Deck Width: 11.00 m
Effective Simply Supported Span (center to center of Bearings): 11.0 m Reinforced Concrete Deck (no G/E)B	LIVE LOAD: IRC 1 Lane of 70R or 1 or 2 Lanes of Class A, whichever governs, and Footpath Loading

Drw. No.: 217 of 4-Webbed RC-Slab-Deck 15.0 m-SS Spa

Reviewed by: Smt Kumar Varna Engineer, DoR	Forwarded by: Jibendra Mishra (SOE, DoR)	Date: June, 2021
Recommendation by: Sak Shrestha	Approved by: Ajay Jung Thapa	Revised:

सहानिबन्धक



SCALE - 1 : 100 @ A3 PAPER



SCALE - 1:100 @ A3 PAPER



SCALE - 1 : 100 @ A3 PAPER




SCALE - 1:100 @ A3 PAPER

S.N.	ITEM	QUANTITY
1.	STRUCTURAL CONCRETE M36 IN 4' WEBBED SLAB / DECK M36 IN FOOTPATH SLAB, ROAD KERB AND PARAPET POST.	69.0 CU.M. 11.0 CU.M.
2.	REINFORCEMENT BARS 500 Mpa (Fe 500)	17.8 TONNES
3.	ASPHALTIC / PREMK WEARING COURSE	117.0 SQ. M.
4.	75MM DIA HEAVY DUTY GI PIPE (RAILING)	93.0 M.
5.	DRAINAGE SPOUTS EACH 450mm LONG Ø100mm G.I. PIPE	8 NOS.
6.	BEARINGS - ELASTOMERIC BRIDGE BEARING	8 NOS.
7.	40mm THICK CONCRETE TILES FOR FOOTPATH	40 SQ. M.
8.	EXPANSION JOINT	22 R.M.


1. EXACT QUANTITIES SHALL BE CALCULATED BY THE CONCERNED ENGINEER FOR COSTING PURPOSES.
2. TOTAL WEIGHT OF ENTIRE SUPERSTRUCTURE IN ONE SPAN = 223 Tonnes.
3. CONCRETE TILES CAN BE REPLACED WITH M20 CONCRETE IN REMOTE AREAS.






REINFORCEMENT DETAILS OF DECK - PLAN VIEW

SCALE - 1 : 100 @ A3 PAPER




REINFORCEMENT DETAILS OF DECK - SECTIONAL VIEW (SEC 4 - 4)

SCALE - 1 : 50 @ A3 PAPER




REINFORCEMENT DETAILS OF PARAPET POST - SECTIONAL VIEW

SCALE - 1 : 25 @ A3 PAPER




REINFORCEMENT DETAILS OF ROAD KERB - SECTIONAL VIEW

SCALE - 1 : 25 @ A3 PAPER




SECTIONAL VIEW OF POST (SEC 5 - 5)

SCALE - 1 : 50 @ A3 PAPER




ELEVATION VIEW OF PARAPET POST

SCALE - 1 : 50 @ A3 PAPER



HALF SECTIONAL PLAN VIEW OF PRECAST R.C. FOOTPATH SLAB

SCALE - 1 : 50 @ A3 PAPER



SECTIONAL DETAIL (SEC 7 - 7)

SCALE - 1 : 50 @ A3 PAPER



SECTIONAL DETAIL (SEC 8 - 8)

SCALE - 1 : 50 @ A3 PAPER


SECTIONAL REINFORCEMENT DETAILS OF PARAPET POST (SEC 6 - 6)

SCALE - 1 : 20 @ A3 PAPER

NOTES:


- Concrete flooring tiles on footpaths in urban area and bituminous approach road. In other region 50 mm thick M20 Concrete flooring above concrete precast slab can be provided for smooth surface in footpaths.
- Maximum width of footpath slab is 1.0m and end footpath slab shall be of appropriate size.

GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS BRIDGE BRANCH	
STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGES	
Revised by: Anil Kumar Vajrakis (Engineer, DoR) Approved by: Dipak Shrestha (DOG, DoR)	Checked by: Anil Kumar Vajrakis (Engineer, DoR) Approved by: Anil Kumar Vajrakis (Engineer, DoR)
Revised by: Anil Kumar Vajrakis (Engineer, DoR) Approved by: Dipak Shrestha (DOG, DoR)	Checked by: Anil Kumar Vajrakis (Engineer, DoR) Approved by: Anil Kumar Vajrakis (Engineer, DoR)
Revised by: Anil Kumar Vajrakis (Engineer, DoR) Approved by: Dipak Shrestha (DOG, DoR)	Checked by: Anil Kumar Vajrakis (Engineer, DoR) Approved by: Anil Kumar Vajrakis (Engineer, DoR)




REINFORCEMENT DETAILS OF EXTERNAL MAIN GIRDER - LONGITUDINAL HALF SECTIONAL VIEW

SCALE: 1: 100 @ A3 PAPER




SECTIONAL DETAIL (SEC 10 - 10)

SCALE: 1: 50 @ A3 PAPER




SECTIONAL DETAIL (SEC 11 - 11)

SCALE: 1: 50 @ A3 PAPER




SECTIONAL DETAIL (SEC 12 - 12)

SCALE: 1: 50 @ A3 PAPER




SECTIONAL DETAIL (SEC 13 - 13)

SCALE: 1: 50 @ A3 PAPER




EXTERNAL MAIN GIRDER BAR ARRANGEMENT DETAIL (DETAIL AT C)

SCALE: 1: 10 @ A3 PAPER




INTERIOR MAIN GIRDER BAR ARRANGEMENT DETAIL (DETAIL AT D)

SCALE: 1: 10 @ A3 PAPER




REINFORCEMENT DETAILS OF INTERIOR MAIN GIRDER - LONGITUDINAL HALF SECTIONAL VIEW

SCALE: 1: 100 @ A3 PAPER




SECTIONAL DETAIL (SEC 14 - 14)

SCALE: 1: 50 @ A3 PAPER




SECTIONAL DETAIL (SEC 15 - 15)

SCALE: 1: 50 @ A3 PAPER



SECTIONAL DETAIL (SEC 16 - 16)


SCALE: 1: 50 @ A3 PAPER




SECTIONAL DETAIL (SEC 17 - 17)

SCALE: 1: 50 @ A3 PAPER


GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS BRIDGE DIVISION			
STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGE		Overall Deck Width: 11.00 m	
Road Carriageway Width: 7.50 m with 2 Footpaths each 1.50 m wide		LIVE LOAD: IRC 1 Lane of 70P or 1 or 2 Lanes of Class A, whichever governs, and Footpath Loading	
Effective Simply Supported Span (center to center of Bearings): 11.2 m Railroad/Ground Concrete Deck (on STEEL)		Design No.: 57 of 4-Webbed RC-Slab-Deck 15.0 m-S5 Span	
REINFORCEMENT DETAILS OF LONGITUDINAL GIRDER			
Reviewed by: Anil Kumar Vamsi (Engineer, DoR)	Forwarded by: Jyotsna Mishra (SDE, DoR)	Date: June 2021	
Recommendation by: Omprakash Shrestha (DDO, DoR)	Approved by: Anil Kumar Vamsi (Engineer, DoR)		




REINFORCEMENT DETAILS OF MID CROSS GIRDER - LONGITUDINAL HALF SECTIONAL VIEW
SCALE - 1:100 @ A3 PAPER




SECTIONAL DETAIL (SEC 18-18)
SCALE - 1:50 @ A3 PAPER




ISOMETRIC DETAIL VIEW OF EXPANSION JOINTS DETAILS AT ABUTMENT
SCALE - NON




DETAIL OF MESH (BAR - EC6)
SCALE - 1:50 @ A3 PAPER




REINFORCEMENT DETAILS OF END CROSS GIRDER - LONGITUDINAL HALF SECTIONAL VIEW
SCALE - 1:100 @ A3 PAPER




SECTIONAL DETAIL (SEC 19-19)
SCALE - 1:50 @ A3 PAPER




EXPANSION JOINTS DETAILS AT ABUTMENT
SCALE - 1:40 @ A3 PAPER




INSTALLATION OF BEARINGS WHEN SUPERSTRUCTURE IS AT GRADE
SCALE - 1:100 @ A3 PAPER




EXPANSION JOINT ISOMETRIC VIEW - SEAL TYPE
SCALE - 1:100 @ A3 PAPER



DRAINAGE SPOUT DETAIL
SCALE - 1:40 @ A3 PAPER



EXPANSION JOINTS ARRANGEMENT IN A CARRIAGEWAY
SCALE - 1:20 @ A3 PAPER



LONGITUDINAL CAMBER PROFILE TO BE GIVEN TO SOFFIT OF DECK
SCALE - NON

Load Condition	Data for Substructure and Foundation Design				Remarks
	Right Exterior Girder	Inner Girder 1	Inner Girder 2	Left Exterior Girder	
Dead Load (Slab and Girder)	181.52	216.22	216.22	181.52	
SDL, Wearing Course	Negligible	42.19	42.19	Negligible	
SDL, Railing and Utilities	95.27	Negligible	Negligible	95.27	
Pedestrian Load	60.09	Negligible	Negligible	60.09	
2 Lane of IRC Class A	198.11	169.22	140.33	111.44	Excluding I.F.
IRC Class 70 R (Tracked)	213.61	170.10	126.59	83.07	Excluding I.F.
IRC Class 70 R (Wheel)	240.65	189.95	139.25	88.56	Excluding I.F.

DATA FOR BEARINGS		
Load Condition	Rate	On each Neoprene Bearing
Under Maximum Live Load	V	585 kN
	H ₁	89 kN
	H ₂	50 kN
	B	0.004540 radian
	Δ	12 mm

NOTES:
 "V" = Vertical Load
 "H₁" = Longitudinal Horizontal Force
 "H₂" = Transverse Horizontal Force
 "B" = Rotation About Bridge Transverse Axis
 "Δ" = Longitudinal Movement for Design Purpose
 "S" = Shear Rating of Bearing

GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS BRIDGE BRANCH		
STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGES		
Road Carriageway Width: 7.5m with 2 Footpaths each 1.5m wide	Overall Deck Width: 11.00 m	
Effective Simply Supported Span (center to center of Bearings): 161 m Reinforced Concrete Deck (in SOCR)	LIVE LOAD: IRC 1 Lane of 10R or 1 or 2 Lane of Class A, whichever governs, and Footpath Loading	
Dwg. No.: 47 of 4-Webbed RC-Slab-Deck 15.0 m-SR Span		
REINFORCEMENT DETAILS OF CROSS GIRDER & MISCELLANEOUS DETAILS		
Reviewed by: Arun Kumar Vamsi (Engineer, DoR)	Forwarded by: Jyotsna Mehta (SCE, DoR)	Date: June, 2009
Recommended by: Dipak Chandra (DO, DoR)	Approved by: Arjun Singh Thapa (DO, DoR)	Signature:

BAR BENDING SCHEDULE OF EXTERIOR MAIN GIRDER (1NO)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	EMG 1		32	16220	8	129.76	819.17
2	EMG 2		32	15750	4	63.00	397.72
3	EMG 3		32	12000	2	24.00	151.91
4	EMG 4		32	8250	2	16.50	104.16
5	EMG 5		20	16220	4	64.88	159.99
6	EMG 6		10	15420	12	185.04	114.17
7	EMG 7		12	5480	92	504.16	447.69
8	EMG 8		32	245	44	10.78	68.05
Total Weight (KG)						2252.48	

BAR BENDING SCHEDULE OF INTERIOR MAIN GIRDER (1NO)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	IMG 1		32	16220	8	129.76	819.17
2	IMG 2		32	15750	2	31.50	198.86
3	IMG 3		32	12000	2	24.00	151.91
4	IMG 4		32	8250	2	16.50	104.16
5	IMG 5		20	16220	4	64.88	159.99
6	IMG 6		10	15420	12	185.04	114.17
7	IMG 7		12	5480	92	504.16	447.69
8	IMG 8		32	245	44	10.78	68.05
Total Weight (KG)						2033.62	

BAR BENDING SCHEDULE OF DECK SLAB (1NO)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	S1		12	11120	156	1734.72	1540.43
2	S2		12	11120	106	1174.72	1040.43
3	S3		12	15620	74	1155.88	1025.42
4	S4		12	15620	74	1155.88	1025.42
5	S5		12	1700	316	537.20	477.03
Total Weight (KG)						5910.74	

BAR BENDING SCHEDULE OF MID CROSS GIRDER (1NO)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	MC1		20	9570	6	57.42	141.60
2	MC2		20	9570	4	38.28	94.40
3	MC3		10	2050	47	96.35	59.45
4	MC4		10	9270	8	74.16	45.76
5	MC5		20	220	18	3.96	2.44
Total Weight (KG)						343.64	

BAR BENDING SCHEDULE OF END CROSS GIRDER (1NO)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	EC1		20	9570	6	57.42	141.60
2	EC2		20	9570	6	57.42	141.60
3	EC3		10	2050	47	96.35	59.45
4	EC4		10	9270	8	74.16	45.76
5	EC5		20	220	18	3.96	9.77
6	EC6		10	1600	3	4.80	2.96
Total Weight (KG)						401.13	

BAR BENDING SCHEDULE OF PARAPET POST BASE (1 SIDE)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	MS1		10	1470	104	152.88	94.33
2	MS2		10	15420	6	92.52	57.06
BAR BENDING SCHEDULE OF RAILING POST (1 SIDE = 5NOs)							
3	MS3		16	2170	36	78.12	123.98
4	MS4		8	560	63	35.28	13.94
Total Weight (KG)						289.32	

BAR BENDING SCHEDULE OF ROAD KERB (1 SIDE)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	MS5		10	1650	104	171.60	105.88
3	MS6		10	15420	6	92.52	57.06
Total Weight (KG)						162.96	

BAR BENDING SCHEDULE OF FOOTPATH PRE CAST SLAB (1NO)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	MS7		8	1210	9	10.89	4.30
2	MS8		8	920	11	10.12	4.00
3	MS9		10	1210	9	10.89	6.72
4	MS10		10	920	11	10.12	6.24
Total Weight (KG)						21.26	

GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS BRIDGE BRANCH			
Road Construction Width: 15m with 3 Footpaths each 3.5m wide		Overall Deck Width: 11.08 m	
Effective Simply Supported Span (Center to center of Bearings): 11.0 m Reinforced Concrete Deck (No. 9000)		LIVE LOAD: IRC 1 (Lane of 75K or 1 or 2 Lanes of Class A, whichever governs, and Footpath Loading)	
Drg. No.: 717 of 4-Wheeled RC-Slab-Deck 15.0 m-SS Span			
BAR BENDING SCHEDULE			
Reviewed by: Anil Kumar Varna (Engineer, DoR)	Prepared by: Jibendra Mishra (SCE, DoR)	Checked by: [Signature]	Date: June, 2021
Recommended by: Chand Sheelwa (DO, DoR)	Approved by: Ajay Jung Thapa (DO, DoR)	Revised by:	Revised: