

Final Copy



GOVERNMENT OF NEPAL
MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT
DEPARTMENT OF ROADS
BRIDGE BRANCH

STANDARD SUPERSTRUCTURE DRAWINGS FOR ROAD BRIDGES

20.0m Simply Supported Span, Cast - in - situ,

Reinforced Concrete Slab - Deck

SKEW ANGLE : 0° to 15°

(CARRIAGE WIDTH - 6.0m WITH BOTH SIDE FOOTPATH - 1.25m = TOTAL WIDTH - 8.50m)

REFERENCE NOTES

- All Dimensions are in millimeters, unless stated otherwise.
- No dimension shall be scaled from the Drawings; only written dimensions shall be followed.
- Any doubtful Dimensions/Descriptions shall be brought to the attention of the Engineer-in-charge for any corrections if any before execution of work.

- Number of reinforcement bars shall not be counted from the Drawings. Only given spacing and specified number of bars shall be provided.
- All materials and workmanship shall be in accordance with these NOTES and those in the stated Drawings and shall be generally in accord with the applicable Specifications and relevant Standards/Codes of Practice specified therein and Sound Engineering Practice, in this order.

- This Bridge Superstructure is designed for One Lane of IRC Class 75B Loading, Two Lanes of IRC Class A Loading and One Lane of IRC Class A Loading, whichever provides, in addition to a Footpath Live Load corresponding to 500 kg/m². This Footpath area is as per Clause 206.3 of IRC - 6 (2017). However, the present Footpath area has also been designed for a wheel Load of 4 Tones distributed over a contact area of 300 mm x 60 mm per axle 25.6 kN of IRC - 6 (2017), allowing 25% increase in stresses due to flexure.

- The Contractor shall be responsible for constructing and maintaining all parts of the structure in stable, acceptable and serviceable condition, ensuring no part under construction is unduly exposed and unsafe.

- CONSTRUCTION SEQUENCE:** Enter Deck (i.e. the Superstructure comprising the cast in situ Reinforced Concrete (or casted slab) shall preferably be constructed in one operation in one day for one span. If this is not possible, then the two spans shall be cast one after the other (each span) up to 150 mm below the top board, i.e. 200 mm, if possible otherwise on two successive days, one after the other, using the Cross Girders, and then the slab cast on the next day. This entire Deck must be cast in-situ on girders, in span to span, not more than three Successive Days.

CEMENT:

- High strength Ordinary Portland Cement 53 Grade, conforming to IS: 12269 or 43 Grade conforming to IS: 8112, capable of achieving the required design concrete Strength and Durability, shall be used.
- Cement shall be obtained from approved Manufacturers only.
- Cement content in the Concrete Mix for Reinforced Concrete shall not be less than 300 kg/m³ and not more than 450 kg/m³.

COARSE AND FINE AGGREGATES:

- Maximum size of Coarse Aggregate used shall be 20mm. Fineness Modulus of Sand (Fine Aggregate) shall not be less than 2.3. Both these Aggregates shall be of Approved Quality, from Approved Sources, and of Approved Gradations, after conforming to IS: 303 (1970). In zones of congestion in the structural sections, if absolutely necessary, 12 mm. down sized Coarse Aggregates may be used but the Mix shall then be re-designed to suit.
- In zones of congestion in the structural sections, if absolutely necessary, 12 mm down sized coarse Coarse Aggregates may be used but the Mix shall then be re-designed to suit.

- ADDITION:** To suitably improve workability and increase initial setting time of concrete and cement grout, Additives conforming to IS: 9103, and ASTM C-494 Type I Water-reducing, High range admixtures, shall be permitted in appropriate dosages, subject to their satisfactory proof use.

REINFORCEMENT:


- All reinforcing steel bars shall be High Yield Strength Deformed type and Thermally Mechanically Treated, having specified minimum 0.2 per cent proof stress of 500 MPa conforming to IS: 1786.
- Minimum lap-length of reinforcement bars shall be 60d where d is the dia of the smaller bar to be lapped (unless otherwise specified).
- Not more than 50 percent of reinforcement crossing a section shall be lapped at that location.
- All laps in reinforcement shall be properly staggered and minimum distance between the laps shall be 1.3 times the lap length.
- Bending of reinforcement bars shall be as per IS: 2002.

- WATER:** Water for concrete and for its curing shall be of potable quality and presence of any salts, sulphates and alkalis shall be checked, sulphates, alkalis, etc. shall be well within their limits specified in the relevant Specifications.

CONCRETE AND CONCRETING

- WATER-CEMENT RATIO:** by weight, shall not exceed 0.45 for Reinforced concrete.
- MINIMUM CLEAR CONCRETE COVER:** to reinforcement bars shall be 40mm.
- CONTROL OF SURFACE CONCRETION**

SURFACE EVAPORATION FROM PLASTIC CONCRETE



Use the graphical Figure below to estimate and control the loss of water through surface evaporation in the laid concrete and 0 or more of the following actions shall be taken to reduce the surface evaporation rate to no more than one kilogram of water per square meter of surface area per hour:

- Construct Windbreaks to effectively reduce the wind velocity (to suit) in the area of concrete placement. The construction of windbreakers or enclosures should not proceed without approval of the Engineer with respect to their structural design relative to safety, stability, adverse loads, and vibrations in the take-out.
- Install automatic Fog Sprayers coupled of the concreting operation to effectively increase the relative humidity in the area of concrete placement.
- When necessary, effectively reduce the temperature of concrete (in suit) by cooling one or more of its components as well as lightly spray the concrete and the laid reinforcement, i.e., if added to the mix-water, shall be completely sealed prior to using that water.

GRADES OF CONCRETE

The structural concrete involved in this Bridge Deck shall be suitably designed as High Strength Concrete Mixes having 28 days minimum water Cube Crushing Strength in Compression on 150 mm Standard Cubes as follows:

For the cast in situ (old) Reinforced Concrete Slabs/Girders, Slab and Cross-girders	35 MPa (i.e. M-35 Grade Concrete)
For the Reinforced Concrete in: Pre-cast Footpath Slabs, Parapet Walls and their Bases, Road Pavement	35 MPa (i.e. M-35 Grade Concrete)

CONSTRUCTION JOINTS:

- As far as possible the location of Construction joints shall be as shown in the Drawings, but if not shown on the Drawings but found absolutely necessary, they shall be planned in advance and the placing of concrete carried out continuously from joint to joint.
- A Construction joint should not be located near the central line of the section as here transverse SHEAR stress is highest. The joint should be nearly perpendicular to the principal lines of tensile stress and in general be located at points of minimum shear and minimum moment - as far as possible.
- Where downers, reinforcing bars, or other obstructions are not shown at Construction joints in the Drawings, 'keys' should be formed if reasonable spacing by embedding water-soaked burlap liners while the concrete is still soft.
- These keys should be sized as may be shown in the details, or as directed by the Engineer, and these key-forming liners shall be removed when the concrete has fully set.
- In resuming concreting work, the surface of the concrete previously placed shall first be thoroughly cleaned of dirt, form oil, laitance, loose concrete aggregates, and any other soft material, using steel wire brushes, and, if deemed necessary by the Engineer, to jetted blasting.
- The concrete surface shall then be thoroughly soaked with clean water (just before further concreting) and the free water, etc. all blown away and the cleaned concrete surface painted with a thin layer of cement slurry, and only then further concrete poured.

- 'Weld-in' and other similar items do not provide a proper construction joint, and they shall not be used.

F. COLD JOINTS:

- When a planned 'horizontal' placement of concrete in any structural member is interrupted or delayed, for any reason, for a period long enough for the previously partially placed concrete to take its initial set, the Engineer may declare such a joint as a Cold Joint and the Contractor shall immediately remove the previously partially placed concrete from the forms.
- However, where feasible, the previously partially placed concrete may instead be suitably and carefully hacked and its top edge brought into 'low shear low moment' zone as far as possible, and given shear key dimensions after bringing it nearly perpendicular to the principal lines of tensile stress (for example, brought to vertical or nearly vertical in a beam with principal bending reinforcement horizontal), and thereafter some treatment shall be given to it as to a Construction Joint and only then the concreting resumed (making sure all reinforcements are as per the approved Drawings and the Scaffolding has been brought to line and plumb tight).

G. CURING AND PROTECTION OF YOUNG CONCRETE:

- All structural concrete shall be kept for a period of time required to obtain the specified strength but not for less than fourteen consecutive days (see notes) beginning immediately after initial setting of concrete (which is when it sets in surface finish).
- Curing (Membrane-curing or Water-curing) of laid concrete shall be carried out as generally explained below:

A. Membrane-Curing the Concrete

- Except for at Construction Joints and surfaces sealed by Forms, liquid membrane curing compound can be used for curing the concrete as follows:
- On bridge deck top surface and other exposed surfaces, liquid membrane curing compound shall be applied soon after initial setting and as the Surface Slab has disappeared and the concrete is still slightly damp (not wet).
- On slabs (i.e. formed vertical surfaces), Forms shall be stripped as soon as practicable (generally after 24 hours of casting) and liquid membrane curing compound applied immediately except in the areas that require rubbing or finishing during the curing period.
- These areas shall be kept water-tight until their finishing is completed, where after the liquid curing membrane shall be uniformly applied on them also when their surface is smooth.
- While (lighter) liquid membrane curing compound shall be used for all surfaces where the structure temperature during curing period is likely to reach about 35°C or more.

- For bridge decks which are to receive an asphaltic overlay, residual curing membrane (after curing) shall be removed prior to the overlaying.
- Removal methods and results should be approved by the Engineer.
- The membrane curing compound used shall be of longer lasting duration and in accordance with the requirements specified for curing membrane material, AASHTO M 148 or its equivalent Specification.

- The curing membrane shall be applied in two applications one immediately following the other.
- The rate of each application of curing compound shall be as prescribed by the manufacturer with a spreading rate per application of at least one liter of liquid per square meter of concrete surface.
- If the concrete has dried up or has become dry, it shall be thoroughly wetted with water and the curing compound applied just as the surface film of water disappears and the surface is damp.

- During curing operations any unexposed surfaces shall be kept cured with watered Hessian cloth, and sprayed with the curing compound when Surface is damp (not wet).
- Any curing membrane material on Construction Joints and/or on reinforcing steel shall be completely removed before the following concrete pour.
- Hand operated spraying equipment shall be capable of applying curing compound under pressure to provide uniform and even distribution of the curing membrane at the sites required.
- The curing compound shall be kept thoroughly mixed at all times during stage of application.
- No traffic of any kind shall be permitted on the curing membrane until the curing process is completed, design permitting.

Water-Curing the Concrete

- All concrete surfaces, unless still sealed by unexposed Forms (which shall be kept from healing up under ambient temperature) or submerged, shall be water-cured without liquid membrane curing.
- Water curing shall begin just after initial setting of concrete (which generally occurs about 16 minutes) of placement of all-structure concrete and after about 120 to 150 minutes of placement of all-structure concrete and just after the surface water has been removed.
- Surface water-cured shall be covered with wet sand, cotton mats, or double-thickness burlap (jute-hessian) sheets.
- The Hessian material shall be placed tightly around and behind any projecting reinforcing steel in order to completely cover the fresh concrete surface.

- The Hessian material shall be completely saturated with water and kept continuously wet throughout the curing period.
- After the water saturation, unless water is kept running, all surfaces shall be covered with thick polythene sheeting or other approved impervious material in order to prevent evaporation drying of concrete surface being cured continuously.
- The sheeting shall be weighed down or secured well to prevent moisture loss but the surfaces of the concrete shall be readily available for inspection of the Engineer on the Representative.
- The sheeting material shall be in good repair.
- Sheeting that contains holes or is otherwise damaged shall be repaired or replaced immediately.
- The Contractor shall be responsible for thoroughly inspecting and monitoring the concrete surfaces throughout the curing period to ensure continuous and correct.
- Additional water shall be poured on any areas where saturation is reduced.
- Inspection of curing by the Contractor shall be conducted at least TEN times per day and night for the duration of the curing period - and even more often if ordered so by the Engineer.
- The Engineer shall be advised if the curing inspection schedule and his (or his Representative) may accompany the workmen to verify the acceptability of curing.

H. 'COLD-WEATHER' CURING:

- When concrete is placed and the air temperature is expected to drop below 5°C during the curing period, the Contractor shall provide suitable measures such as, above, additional curing or other suitable insulating materials and/or heating and artificial hot-air-curing to maintain the concrete temperature between 10°C and 32°C as measured on the surface of the concrete.
- The surface of the concrete shall be kept moist and warm by the use of an approved wetting agent and water-cured concrete shall be kept wet throughout the curing period.
- The moisture barrier should be maintained in intimate surface contact with the concrete during the entire curing period.
- After the completion of the curing during the entire required curing period, the Contractor shall stop the curing and remove the protection in such a manner that rapid cooling of the concrete is prevented.
- When concrete is placed in 'cold-forms' and subsequently flooded with ground water, the above curing operations may be waived, provided the surface of the water is not permitted to freeze.

I. 'CONCRETING' IN 'ADVERSE WEATHER' CONDITIONS:

- 'Concreting' in 'Cold Weather':**
- Concrete that freezes soon after placing, gains rather less strength and some permanent damage is caused. Therefore, such concrete shall be removed and replaced immediately.
- Planning for Protection of fresh concrete, during placement, and until it has attained the minimum properties required for the environment and the loading to which it will be exposed, shall be done with in advance of concreting and approved by the Engineer.
- Appropriate equipment shall be made available in time for heating the concrete materials, for constructing enclosures and for maintaining concrete temperatures even after the concrete is placed.
- Concrete shall never be placed in cold Forms and cold steel.
- When the temperature of these items is below 5°C, the Contractor shall use means to raise their temperature to above 10°C.
- When faced with prolonged cold temperatures, all aggregates, or mixing water, or both, shall be heated to above 25°C to 32°C.
- At temperatures at least 10°C above freezing, it is seldom necessary to heat the Aggregates.
- At temperatures below or at freezing, often only the Fine Aggregate is heated to produce concrete of the required temperature, provided the Coarse Aggregate is free of frozen lumps and its Temperature of water for the Mix is at least 10°C.
- If appropriate temperatures are above freezing, the desired concrete temperature usually can be obtained by heating only the mixing water.

CONTINUE

GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS BRIDGE DIVISION	
STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGES	
Steel Concrete Width 1.5m with 3 Composite width 1.2m wide	Overall Deck Width 1.5m
Effective Span/Support Spacing (Center to center of Bearings) 30.0 m and 30.0 m	LIVE LOAD: IRC 1 (max of 750 kN or 12 m of Class A, whichever governs, and Full-width Loading)
Dep. No. 17-3-Subbed RC-Slab Deck 20.0 m SS-SD	
Dep. TITLE: REFERENCE NOTES (1) Sheet: Street 10	
Reviewed by: Pradip Kumar (Engineer, Civil)	Forwarded by: Jyoti K. Mishra (SCE, Dep't)
Approved by: Dipak Kumar (SCE, Dep't)	Approved by: Anjan Kumar (SCE, Dep't)
Date: June 2021	Date: June 2021

- 1) Appreciable fluctuation in the rising water temperature from batch to batch shall not be allowed.
- B. Concrete in "Hot" Weather**
- ii. No concrete shall be placed when the ambient air temperature at job site is above 32°C.
- iii. When the temperature of the concrete mixer is expected to exceed 32°C, a waiting situation shall be initiated in the approved mix design team setting time limits to reduce a higher temperature.
- iv. The temperature of the concrete mixer immediately before placement shall not exceed 32°C.
- v. When the ambient air temperature is above 32°C, all forms, reinforcing steel, and other contact surface temperature conditions shall be cooled to below 32°C until concrete is placed.
- vi. When such high ambient temperature conditions exist, the most appropriate solution is to resort to setting night & morning low concreting.
- vii. However, if this above stated procedure is unable to help lower the temperature of contact surface and the concrete mix ingredients are also cooled (advanced ahead), concreting can be carried out even during dry hours provided the ambient temperature is made not exceed 40°C.
- viii. Mixers, chutes, belts, hoppers, pump lines, and other production and placement equipment can be shaded.
- ix. Placed water, mixed with (wet) bulps, or otherwise cooled to reduce the effect of the sun's heat.
- x. Forms and reinforcing steel can be sprinkled with cold water and covered with wet burlap until concrete concretion commences.
- xi. Spraying the area with water sprays, carefully coats the contact surfaces and surrounding area and decreases its relative humidity.
- xii. This not only reduces the temperature of the concrete but also minimizes evaporation of water from the concrete during placement and after casting.
- xiii. For slab on ground, it is a good practice to dampen the sub-grade the evening before concreting.
- xiv. There should be to standing water or puddles on the sub-grade or inside the Forms when the concrete is placed.
- xv. The mix water may be cooled by using chiller or crushed ice as well as much ice should be used as will be needed entirely for the water is added to the mix.
- xvi. All water used for making mix and for cooling or sprinkling, and curing, must meet the same quality requirements as those for water used for Mixing of Concrete.
- xvii. Of particular concern are the polluting substances and chloride salts in the mix, which can adversely affect the cement and concrete reinforcing steel, respectively. These must be kept below their specified limits.
- xviii. Aggregate should be kept by shading and sprinkling water (dry spray).
- xix. Transporting and placing concrete shall be done as quickly as practical during hot weather.
- xx. Delayed contribution loss of slump, a damaging increase in concrete temperature and loss of workability.
- xxi. Enough worker and equipment shall always be available to handle and place concrete immediately upon delivery.
- xxii. Prolonged mixing even at stopping stage of the Chute, shall be avoided since it might lead to the mix and lower workability.
- xxiii. If delays occur, the heat generated by continued mismanagement can be minimized by stopping the mixer and then agitating intermittently, but shall not be kept stop.
- xxiv. Such concrete requires more compaction in hot weather, extra care in placing techniques is required to avoid Cold Joints.
- xxv. For placement of Concrete in Walls, Chutes, Columns, etc., shallower layers may be required to assure proper consolidation and monitor only with previous trial, effective dispersion of heat of hydration and to prevent segregation of the mix.
- xxvi. Temporary coverings and windbreakers help to minimize adverse effects of hot weather, which, and surface evaporation.

10. CAUTION AGAINST "PLASTIC-SHRINKAGE" CRACKING of Concrete and USING EXCESSIVE DOSAGES of ADDITIVES like RETARDER and "SUPER" - PLASTICIZER

- i. Plastic Shrinkage cracks develop prior to initial setting of concrete and can appear more prominently in slabs. If the rate of surface evaporation from the freshly cast concrete is faster than the rate of water bleeding through it, the concrete surface tends to dry up, hence shrink, causing cracks in plastic concrete due to tension from this shrinkage under both conditions. These cracks travel downwards from the surface and their propagation is fastest just upon initial setting of concrete.
- ii. The longer the setting setting time, deeper will these cracks penetrate. Shrinkage that travels down to a significant depth of slab, then the slab can become a host of isolated, concrete blocks separated by these cracks, and hence not be structurally monolithic with the rest of the deck section. Such deep penetration cracks, if not immediately sealed, will not separate the Super Fibers of these cracks. The seal may be a major damage, requiring major rehabilitation.
- iii. Hence, minimum doses of Retarders and Super-Plasticizers shall be used so as to keep the initial setting time to just the required minimum to allow the required 'workability' of concrete.

- vi. These cracks can be of random pattern (polygonal-slab pattern) and may be somewhat parallel to each other and nearly perpendicular to the direction of wind that prevailed at the time of casting. Hence the field staff must look for these cracks before the concrete has initially set, and about these cracks occur. The plastic concrete should be quickly "topped" or "blended" so, the surface not re-ventilated to close these cracks at time.
- vii. Concrete slabs which are correctly re-ventilated should not exhibit Plastic Shrinkage cracks because the action of heating and travelling is a form of re-compaction that tends to close them as fast as they are formed. This re-ventilation can, however, require substitution of solids in the mix and cause Plastic Settlement cracks (see ahead).
- viii. Although the Plastic Shrinkage cracks can be wide at their start (even up to 2 mm), the width rapidly diminishes with depth. Nevertheless, in severe cases they may pass through the full depth of a slab, in contrast with most cases of Plastic Settlement cracks. If not noticed at the time of casting, they can be detected through waiting at the top of the slab may show them in case of full depth penetration. Taking cores can reveal them precisely.
- ix. Plastic Shrinkage cracks rarely reach the free ends of the slab (e.g. the edges of a slab) because these edges are free to move under plastic shrinkage. This is a very important aspect differentiating them from long term drying shrinkage cracks. If the time of formation is unknown, however, Plastic Shrinkage cracks will form up to the ends of a slab which has been cast against a previous pour, especially if there is continuity of slab, because this case is resistant.
- x. The factors that determine rate of surface evaporation are: the temperature of the concrete, the air temperature, relative humidity, and wind velocity of the air adjacent to the concrete. The evaporation increases as the humidity decreases, as the wind velocity increases, as the air temperature decreases, and as the concrete temperature increases. Of particular interest is the fact that rapid evaporation is at least as big a problem in cold weather as in hot weather. Even when the relative humidity is 100% and wind is cold weather, there will be a large amount of evaporation if the concrete is warm. If all the factors listed above, only the concrete temperature is easily controllable. There is a definite advantage to cool the concrete. It must be placed as cool as practical in winter weather and should not be over-heated in cold weather. If the concrete temperature is reduced to about 15°C to 17°C, much of the evaporation can be minimized.
- xi. In hot weather, sometimes concreting during 4 p.m. on the previous day up to 12 noon on the next day may be resorted to for preventing formation of Plastic Shrinkage cracks and obtaining better quality concrete, but this will be effective only if it goes significantly below normal temperatures and lower wind velocity. The reduction of temperature BUT not of concrete (even with the increase in relative humidity) will not significantly reduce the Plastic Shrinkage cracking.
- xii. If it is not possible to eliminate the rate of Plastic Shrinkage cracks even by increased windy curing, then chances to the concrete mix must be considered. First, check that the concrete does not contain an admixture that has adverse effects. If it does, try to reduce it or replace it with one that does not, and test as much (rather than counter) by adding a compensating admixture. Second, consider the use of an air entrainment. Air-entrained concrete exhibits less Plastic Shrinkage cracks than plain concrete. If at night the night same logical reason as in air entrainment, the rate of bleeding it should increase the rate of Plastic Shrinkage cracks occurring at a given rate of placement. However, most commercially available air-entraining agents are "delicate" and therefore reduce the surface tension caused by drying, and consequently reduce the shrinkage cracking.
- xiii. The prevention and timely repair of Plastic Shrinkage cracks in slabs is particularly critical, and because the cracks are wide at the top and can rapidly seal in potholes which may cause subsequent spalling and prevent the subsequent satisfactory application of sealing materials. Clearly wide cracks in slabs are not likely to be self-sealing at the top and are likely to split and show signs of potholes.

11. CAUTION AGAINST POSSIBLE DAMAGE TO "PLASTIC SETTLEMENT" CRACKING OF CONCRETE

- i. Plastic Settlement cracks occur in non-fully-cured concrete when there is a relatively high amount of bleeding through it and some form of obstruction to the downward sedimentation of its solids (i.e. the reinforcement bars). These obstructions break the back of the setting concrete over them as the solids fall downwards around them, forming formation of hollow under their belly. Thus Cracks show directly over formwork or bolts or over reinforcement near the top of the plastic concrete, reflecting their pattern. Such Cracks can also occur in narrow columns and walls where the air-ventilation is prevented by the resulting setting of the concrete due to downward passage for sedimentation and there may be further aggravation by the presence of horizontal bars.
- ii. Plastic Settlement cracks can be prevented by reducing the bleeding and hence the sedimentation, and by reducing the obstructions to sedimentation.
- iii. Admixtures such as plasticizers reduce water demand and thus are the most effective way of reducing bleeding and sedimentation. But before the plasticizers are used, the concrete must be eliminated by light vibration, and re-bleeding of the not yet fully-cured concrete if they have formed, thus also stop them the under belly (hollow).

- vi. This light re-vibration shall not be applied too soon otherwise a second phase of bleeding can still cause Plastic Settlement cracks. The correct time can only be determined by simple site trials. It will be the last time that a vibrating point can be inserted into the concrete and removed without leaving a significant plastic Re-vibrator is often the only way to eliminate plastic settlement cracks, particularly in deep slabs. Trowelling the concrete surface will aggravate these cracks as the pressure may only cause further settlement of solids.

12. BEWARE OF CRACKS DUE TO "PLASTIC-SHRINKAGE" AND "PLASTIC SETTLEMENT" IN CONCRETE WHILE IT IS STILL PLASTIC AND HAS NOT YET ATTAINED 'INITIAL SET'

- i. Plastic cracks by their very nature pass through the cement matrix and grout aggregate particles, therefore they are very jagged and capable of transferring stress, providing there is a sufficient reinforcement to maintain aggregate integrity. Consequently full structural repairs (using epoxy formulation) may not be necessary. However, if the cracks are deep, penetration is into the concrete, and the aggregate is exposed, the cracks should be repaired. RUT will resist full monolithically (in which case the deck slab may have to be demolished, re-laying, rapid, and very costly rehabilitation required). HENCE BEWARE OF PLASTIC CRACKING.
- ii. If cracks follow the pattern of the slab reinforcement it may be difficult at all to determine whether they are due to Plastic Shrinkage or Plastic Settlement. If it can be shown that the cracks pass through the slab and follow the pattern of the steel, they are almost certainly Plastic Shrinkage cracks that have been oriented by the steel.
- iii. Plastic cracks often form in the top face of sections e.g., Plastic Shrinkage cracks in slabs, and Plastic Settlement cracks on top of deep beams and walls. They can be accurate, and this coupled with the fact that they form so early in the life of concrete, means that they may extend as thermal contraction and drying shrinkage take place. Consequently it may not be wise to fill plastic cracks with epoxy materials until it is certain that the long-term effects have subsided.
- iv. Plastic Settlement cracks over steel must be immediately and efficiently sealed if the concrete is in an exposed state to maintain the top of concrete of the slab. Reduced bond strengths due to under belly hollows thus formed under steel bars are dangerous.

13. ACCEPTABILITY CRITERIA OF CONCRETE CURING TEST RESULTS FOR APPROVING THE CONCRETE THEY REPRESENT

- i. The acceptability criteria of Standard Cures curing test results shall be that not more than 5% of works under test shall be specified minimum work strength. For this to be fulfilled, the Mean Strength of works under test at 28 days against 1.64 times the 'Standard' Cures strength shall not be less than the required minimum 28 day work strength.
- ii. Alternatively, if the Standard Deviation for the concerned Concrete has not been established, the cure strength shall be accepted as complying with the strength requirement either 'if none of the specimens tested falls below the minimum specified strength' or 'if the average strength of the specimens is not less than the specified minimum work strength, with lower 10% of the minimum specified work strength' and the difference between the maximum and the minimum strength of the test specimens is NOT GREATER THAN 20% of that strength.
- iii. In case of a dispute about the strength of concrete in a particular area of the cast concrete, three 50 mm dia. and 100 mm long Standard concrete cores shall be drilled out from such an individual area and tested for their crushing compressive strength. These values shall be compared for corresponding work strength and the low of the work strength and the corresponding equivalent 'cube' strengths worked out for each core. If their average exceeds 100% of the required 28 days work strength, their concrete is said to be acceptable, but shall be of course subject to constructive comments for poor work.

14. RELEASE OF THE STAGING SUPPORTING THE DECK IN A SPAN AFTER SUCCESSFULLY CURING THE CONCRETE IN THE DECK AS SPECIFIED ABOVE AND THE CONCRETE IN IT ATTAINS A MINIMUM WORK STRENGTH CURING STRENGTH OF 280 kg/cm² (age of Concrete approximately 21 days after casting) the staging supporting the Deck may now be released. The Superstructure (i.e. the Deck) shall not be loaded until after its concrete is at least 28 days old and crushing cube strength of its concrete is 350 kg/cm².

15. BEARINGS

- i. NEOPRENE BEARINGS shall be used. Their Material specifications, Design, Acceptance Criteria and installation shall be generally in accordance with IS 83 part (2) (GSI), the AASHTO Design Specifications, and Sound Engineering Practice.
- ii. The Bearings shall be obtained from approved and experienced Manufacturers.
- iii. Installation of Bearings shall be carried out under the expert supervision of the Manufacturer's Technical Representative.
- iv. The Design of Bearings shall be based on the Design Loads, Rotations, etc., given in the appropriate table in the attached relevant Drawing.
- v. Detailed Drop Drawings shall be prepared by the Manufacturer, which shall be checked and duly approved before the Bearings are manufactured and installed.
- vi. Neoprene Bearings shall be bonded to their R.C. pedestals by appropriate epoxy (e.g. the Groudbonding Bond, where used, shall be with highest strength than 'Bonding New Shrink Type').

- vi. All Bearings shall be placed in dry horizontal plane only and to true line and rotation (unless shown otherwise), as generally indicated in the attached relevant Drawing.
- vii. Use the correct adhesive with proper change the type of Bearings from Neoprene to POT Bearings (POT Fixed and POT PTFE Fixed), then the magnitudes of Vertical loads, Horizontal forces and movements, etc. tabulated in Drg No. 57 of 3-Minibond RC-Slab-Deck 2013 m-SS Span will all change and the same will have to be re-worked out and the design of POT-Bearings done accordingly. The Substructure Foundations shall also be designed according to the correctly re-worked out loads, Forces and Movements, etc.

17. EXPANSION-CONTRACTION JOINTS

- i. These Movement joints shall be provided in the deck as specified and shown in attached relevant Drawing. These shall be of Approved Quality and shall be fitted under the expert supervision of the Manufacturer at the appropriate ambient Temperature as per Design.
- ii. An other type of expansion joint the compression seal, side seal etc. that satisfies the requirements as shown in relevant drawing can also be used under the supervision of concerned Engineer.
- iii. **WEARING COURSE:** Asphaltic concrete / Plastic wearing Course, 75mm thick at roadway crown, gradually reducing to 50mm at the road Kerbs, shall be provided over the Deck Slab.
- iv. **EARTHQUAKE EFFECTS:** The Horizontal Seismic coefficient assumed is 0.18 (i.e. 0.18g) accompanied by a Vertical Seismic coefficient of + or - 0.12g.

20. DESIGN CONSULTANT: Responsible for National Development center (P) Ltd. Lathur, Punjab.

LIST OF DRAWINGS:

DRAWING TITLE	REFERENCE NOTES (2 Sheets) Sheet 1/2	REFERENCE NOTES (2 Sheets) Sheet 2/2
REINFORCEMENT DETAILS OF DECK SLAB, FOOTPATH SLAB, ROAD KERB & PARAPET POST	SUPERSTRUCTURE OUTLINE & REINFORCEMENT DETAILS OF DECK SLAB, FOOTPATH SLAB, ROAD KERB & PARAPET POST	REINFORCEMENT DETAILS OF CROSS GIRDER & MISCELLANEOUS DETAILS
REINFORCEMENT DETAILS OF LONGITUDINAL ORDER	REINFORCEMENT DETAILS OF CROSS GIRDER & MISCELLANEOUS DETAILS	BAR BENDING SCHEDULE

GOVERNMENT OF NEPAL
MINISTRY OF PHYSICS, INFRASTRUCTURE AND TRANSPORT
DEPARTMENT OF ROADS
ROADS BUREAU

STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGES

Revised by: Prakash Kumar (Engineer: DoT)

Checked by: Prakash Kumar (Engineer: DoT)

Approved by: Prakash Kumar (Engineer: DoT)

Drawn by: Prakash Kumar (Engineer: DoT)

Scale: 1:100






Effective Date: 2013-01-01

Project No: 377 of 3-Minibond RC-Slab-Deck 2013 m-SS Span

Dwg. Title: REINFORCEMENT NOTES (2 Sheets) Sheet 2/2

Date: Jan 2021

Page: 90



GENERAL NOTE:





1. ALL DIMENSIONS ARE IN MILLIMETERS, UNLESS STATED OTHERWISE.
2. NO DIMENSIONS SHALL BE SCALE FROM DRAWING, ONLY WRITTEN DIMENSIONS SHALL BE FOLLOWED.
3. MATERIAL GRADE
 - A. CONCRETE GRADE : M35
 - B. STEEL GRADE : Fe500
 - C. COVER : 40mm
4. CHAMFER 15mm x 15mm SHALL BE PROVIDED AT ALL JUNCTIONS OF THE FRAMEWORK UNLESS OTHERWISE SPECIFIED IN THE DRAWING.
5. PROPERLY STIFFENED STEEL PLATES SHALL BE USED WHILE POURING FOR CASTING THE SLAB AND DECK.

S.N.	ITEM	QUANTITY
1.	STRUCTURAL CONCRETE M35 IN DECK AND SLAB M35 IN ROAD KERB (SLAB, ROAD KERB AND PARAPET) POST.	75.0 CU.M. 13.0 CU.M.
2.	REINFORCEMENT BARS 500 MPa (Fe 500)	18.7 TONNES
3.	ASPHALTIC / PREMIX WEARING COURSE	123.0 SQ. M.
4.	75MM DIA G.I PIPE (SALING)	123 M.
5.	DRAINAGE GROUTS EACH 450mm LONG Ø100mm G.I PIPE	8 NOS
6.	BEARINGS - ELASTOMERIC BRIDGE BEARING	6 NOS
7.	40mm THICK CONCRETE TILES FOR FOOTPATH	33.0 SQ. M.
8.	EXPANSION JOINT	17 R.M.

NOTES

1. EXACT QUANTITIES SHALL BE CALCULATED BY THE CONCERNED ENGINEER FOR COSTING PURPOSES.
2. TOTAL WEIGHT OF ENTIRE SUPERSTRUCTURE IN ONE SPAN = 245 Tonnas.
3. CONCRETE TILES CAN BE REPLACED WITH M20 CONCRETE IN REMOTE AREAS.

GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS (RURAL BRANCH)		
STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGES		
Road Carriageway Width: 6.3m with 2 Footpaths each 1.575 m wide	Overall Deck Width: 9.45 m	
Single Slope Support Span center to center of Support: 20.0 m (Roadbed Cross Section is 10/95)	LIVE LOAD: RSC-1 Lane of 130 kN at 2.1 m center of Clear A, wheelbase, position, and Footpath Loading	
Dwg. No. 37 of 4-Webbed RC-Slab-Deck 20.0 m SS Span		
Dwg. TITLE : SUPERSTRUCTURE OUTLINE AND DIMENSIONS		
Reviewed by Prashant Kumar Bhatta (Programmer, DOR)	Forwarded by Rajendra K. Mishra (ASST. DOR)	Date : June 01, 2021
Drawn by Rajendra K. Mishra (ASST. DOR)	Approved by Rajendra K. Mishra (ASST. DOR)	Remarks







Concrete Terra Stone Pavestone
400x400x60mm (JURBAN AREA) OR
M15 50 mm Thick Concrete Flooring
(SMOOTHING FOOTPATH SURFACE)




SECTIONAL REINFORCEMENT DETAILS OF PARAPET POST (SEC 6 - 6)
SCALE - 1:20 @ A3 PAPER

NOTES:

- Concrete flooring tiles on footpaths in urban area and suburban approach road. In other region 50 mm thick M20 Concrete flooring above precast slab can be provided for smooth surface in footpaths.
- Maximum width of footpath slab is 1.0m and end footpath slab shall be of appropriate size.




GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS BRIDGE DIVISION		
STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGES		
Revised Drawing No. 4-10 with 2 Footpaths each 1.50m wide	Overall Deck Width: 3.00 m	
Effective Single Footpath Size (center to center of Footpath): 2.0 m	LIVE LOAD: IRC 1 Lane of 75kN or 1 or 2 Lane of Class A, whichever governs, and Footpath Loading	
Orig. No. 47 of 3 Webbed RC Slab-Deck 26.8 m x 5.8 Span		
REINFORCEMENT DETAILS OF DECK SLAB, FOOTPATH SLAB, ROAD KERB & PARAPET POST		
Reviewed by: Prashant Sharma (Engineer-DOE)	ForWARDED by: Ajay Kumar Sharma (S.A.E.T-DOE)	Date: June, 2021
Recommended by: Dipak Kharel (DOO, DMR)	Approved by: Ajay Kumar Sharma (S.A.E.T-DOE)	Approved by: Ajay Kumar Sharma (S.A.E.T-DOE)




REINFORCEMENT DETAILS OF EXTERNAL MAIN GIRDER - LONGITUDINAL HALF SECTIONAL VIEW

SCALE: 1:100 @ A3 PAPER




SECTIONAL DETAIL (SEC 10-10)

SCALE: 1:50 @ A3 PAPER




SECTIONAL DETAIL (SEC 11-11)

SCALE: 1:50 @ A3 PAPER




SECTIONAL DETAIL (SEC 12-12)

SCALE: 1:50 @ A3 PAPER




SECTIONAL DETAIL (SEC 13-13)

SCALE: 1:50 @ A3 PAPER




REINFORCEMENT DETAILS OF INTERIOR MAIN GIRDER - LONGITUDINAL HALF SECTIONAL VIEW

SCALE: 1:100 @ A3 PAPER




SECTIONAL DETAIL (SEC 14-14)

SCALE: 1:50 @ A3 PAPER




SECTIONAL DETAIL (SEC 15-15)

SCALE: 1:50 @ A3 PAPER




SECTIONAL DETAIL (SEC 16-16)

SCALE: 1:50 @ A3 PAPER




SECTIONAL DETAIL (SEC 17-17)

SCALE: 1:50 @ A3 PAPER



EXTERNAL MAIN GIRDER BAR ARRANGEMENT DETAIL (DETAIL AT C)


SCALE: 1:10 @ A3 PAPER




INTERIOR MAIN GIRDER BAR ARRANGEMENT DETAIL (DETAIL AT D)

SCALE: 1:10 @ A3 PAPER


GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS BIRATNAR	
STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGES	
Road Carriageway Width: 6.0m with 3 Footpaths each 1.25m wide	Overall Deck Width: 9.50m
Effective Simple Supported Span (centre to centre of Bearings): 30.0m Reinforced Concrete Deck (see 5038)	LIVE LOAD: IRC 1 Lane of 75k or 1 or 2 Lanes of Class A, with lane spacers, and Forward Loading
Fig. No.: 57 of 3-Webbed RC-Slab Deck 20.3 m-SGS Span	
REINFORCEMENT DETAILS OF LONGITUDINAL GIRDER	
Reviewed by: President's Formula (Engineer, Civil)	Forwarded by: Jyoti Malla (S.D.O., Civil)
Recommended by: Dipak Shrestha (S.D.O., Civil)	Approved by: Ankur Thapa (S.D.O., Civil)
Date: June 2021	Remarks:




REINFORCEMENT DETAILS OF MID CROSS GIRDER - LONGITUDINAL HALF SECTIONAL VIEW
SCALE - 1:100 @ A3 PAPER




SECTIONAL DETAIL (SEC 18-18)
SCALE - 1:50 @ A3 PAPER




ISOMETRIC DETAIL VIEW OF EXPANSION JOINTS DETAILS AT ABUTMENT
SCALE - NON




DETAIL OF MESH (BAR - EC5)
SCALE - 1:50 @ A3 PAPER




REINFORCEMENT DETAILS OF END CROSS GIRDER - LONGITUDINAL HALF SECTIONAL VIEW
SCALE - 1:100 @ A3 PAPER




SECTIONAL DETAIL (SEC 19-19)
SCALE - 1:50 @ A3 PAPER



EXPANSION JOINTS DETAILS AT ABUTMENT
SCALE - 1:40 @ A3 PAPER




INSTALLATION OF BEARINGS WHEN SUPERSTRUCTURE IS AT GRADE
SCALE - 1:100 @ A3 PAPER




EXPANSION JOINT ISOMETRIC VIEW - SEAL TYPE
SCALE - 1:100



DRAINAGE SPOUT DETAIL
SCALE - 1:40 @ A3 PAPER



EXPANSION JOINTS ARRANGEMENT IN A CARRIAGEWAY
SCALE - 1:20 @ A3 PAPER



LONGITUDINAL CAMBER PROFILE TO BE GIVEN TO SOFFIT OF DECK
SCALE - NON

Data for Substructure and Foundation Design				
Load Condition	Reaction (kN)			Remarks
	Right Exterior Girder	Inner Girder 1	Left Exterior Girder	
Dead Load (Slab and Girder)	281.47	313.44	281.47	
SIDL, Wearing Course	22.50	45.00	22.50	
SIDL, Railing and Utilities	87.73	Negligible	87.73	
Pedestrian Load	43.60	Negligible	43.60	
2 Lane of IRC Class A	232.15	238.11	244.08	Excluding I.F.
IRC Class 70 R (Tracked)	242.85	205.68	170.51	Excluding I.F.
IRC Class 70 R (Wheel)	298.14	247.94	197.73	Excluding I.F.

DATA FOR BEARINGS		
Load Condition	Name	On each Neoprene Bearing
Under Maximum Live Load	V	740 kN
	H ₁	112 - 62 kN
	H ₂	82 kN
	Δ	0.00484 Radian
	Δ	10 mm

NOTES :
 "V" = Vertical Load
 "H₁" = Longitudinal Horizontal Force
 "H₂" = Transverse Horizontal Force
 "Δ" = Rotation About Bridge Transverse Axis
 "Δ" = Longitudinal Movement for Design Purpose
 "C" = Shear Rating of Bearing

 GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS BRIDGE DIVISION			
STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGES			
Road Carriageway Width: 5.50 m with 1 Footpath each 1.25 m wide		Overall Deck Width: 6.30 m	
Effective Simply Supported Span (center to center of bearings): 30.0 m and Footpath Loading		LIVE LOAD: IRC 1 Lane of 70R or 1 or 2 Lane of Class A, whichever governs, and Footpath Loading	
Dwg. No.: 87 of 3-Webbed RC-Slab-Deck 20.0 m-SB Span			
REINFORCEMENT DETAILS OF CROSS GIRDER & MISCELLANEOUS DETAILS			
Prepared by Praduman Koirala (Engineer, Draft)	Checked by Jyoti Koirala (SCE, Draft)	Approved by Ajay Jung Thapa (SCE, Draft)	Date June, 2021
Reapproved by Sagar Shrestha (SCE, Civil)			Revision 00

BAR BENDING SCHEDULE OF EXTERIOR MAIN GIRDER (1NO)						
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)
1	EMG 1		32	21220	10	212.20
2	EMG 2		32	19500	2	39.00
3	EMG 3		32	14500	4	58.00
4	EMG 4		32	9600	4	38.00
5	EMG 5		20	21220	4	84.88
7	EMG 6		10	20420	12	245.04
8	EMG 7		12	6680	120	801.60
9	EMG 8		32	245	60	20.09
Total Weight (Kg)						339.03

BAR BENDING SCHEDULE OF INTERIOR MAIN GIRDER (1NO)						
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)
1	IMG 1		32	21220	8	169.76
2	IMG 2		32	19500	2	39.00
3	IMG 3		32	14500	4	58.00
4	IMG 4		32	9600	4	38.00
5	IMG 5		20	21220	4	84.88
6	IMG 6		10	20420	12	245.04
7	IMG 7		12	6680	120	801.60
8	IMG 8		32	245	60	20.09
Total Weight (Kg)						3123.10

BAR BENDING SCHEDULE OF DECK SLAB (1NO)						
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)
1	S1		12	8620	206	1775.72
2	S2		12	8620	206	1775.72
3	S3		12	20520	58	1190.16
4	S4		12	20520	58	1190.16
5	S5		12	1700	312	530.42
Total Weight (Kg)						5948.70

BAR BENDING SCHEDULE OF MID CROSS GIRDER (1NO)						
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)
1	MC1		20	6570	8	52.56
2	MC2		20	6570	4	26.28
3	MC3		10	2490	32	75.60
4	MC4		10	6270	8	50.16
5	MC5		20	220	16	3.52
Total Weight (Kg)						243.78

BAR BENDING SCHEDULE OF END CROSS GIRDER (1NO)						
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)
1	EC1		20	6570	6	39.42
2	EC2		20	6570	6	39.42
3	EC3		10	2490	30	74.70
4	EC4		10	6270	8	50.16
5	EC5		20	220	16	3.52
6	EC6		10	1000	2	2.00
Total Weight (Kg)						285.42

BAR BENDING SCHEDULE OF PARAPET POST BASE (1 SIDE)						
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)
1	MB1		10	1470	127	206.79
2	MB2		10	20420	6	122.52
Total Weight (Kg)						369.41

BAR BENDING SCHEDULE OF RAILING POST (1 SIDE = 11Nos)						
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)
3	MS3		16	2170	44	95.48
4	MS4		8	960	77	43.12
Total Weight (Kg)						369.41

BAR BENDING SCHEDULE OF ROAD KERB (1 SIDE)						
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)
1	MR5		10	1650	137	226.05
3	MR6		10	20420	5	102.10
Total Weight (Kg)						215.07

BAR BENDING SCHEDULE OF FOOTPATH PRE CAST SLAB (1NO)						
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)
1	MS7		8	710	9	6.39
2	MS8		8	520	7	3.64
3	MS9		10	710	8	5.68
4	MS10		10	520	7	3.64
Total Weight (Kg)						12.96

GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS BRIDGE BRANCH		
STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGE		
Road Carriageway Width: 6.0m with 2 Footpaths each 1.50m wide	Overall Deck Width: 9.00 m	
Effective Simply Supported Span (center to center of bearings): 20.0 m Reinforced Concrete Deck (No. 200)	LIVE LOAD: IRC-1 Lane of 75k or 1 or 2 Lanes of Class A, whichever governs, and Forward Loading	
Dwg. No.: 77 of 3-Webbed RC-Deck 20.0 m-SS Span		
BAR BENDING SCHEDULE		
Reviewed by: Pradip Kumar (Engineer, DOP)	Forwarded by: Jyoti Mishra (S.D.O., DOP)	Date: June 2021
Recommended by: Dipak Shrestha (D.O., DOP)	Assessed by: Arjun Jung Thapa (S.D., DOP)	Revisions: 00

डिपक श्रेष्ठ
 डिपक श्रेष्ठ