

Final Copy



GOVERNMENT OF NEPAL
MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT
DEPARTMENT OF ROADS
BRIDGE BRANCH

STANDARD SUPERSTRUCTURE DRAWINGS FOR ROAD BRIDGES

25.0m Simply Supported Span, Cast - in - situ,

Reinforced Concrete Slab - Deck

SKEW ANGLE : 0° to 15°

(CARRIAGE WIDTH - 6.0m WITH BOTH SIDE FOOTPATH - 1.25m = TOTAL WIDTH - 8.50m)

REFERENCE NOTES:

- All dimensions are in millimeters, unless stated otherwise.
- No dimension shall be scaled from the Drawings; only written dimensions shall be followed.
- Any doubtful Dimensions/Descriptions shall be brought to the attention of the Engineer-in-charge for any clarifications if and before execution of work.
- Number of reinforcement bars shall not be counted from the Drawings. Only given spacing and/or specified numbers of bars, shall be provided.
- All materials and workmanship shall be in accordance with these NOTES and those in the latest Drawings and shall be generally in accord with the applicable Specifications and relevant Standards/Codes of Practice specified therein and Standard Engineering Practice, if not clear.
- This Bridge Superstructure is designed for One Lane of IRC Class 70R Loading, Two Lanes of IRC Class A Loading, and One Lane of IRC Class A Loading, whichever governs, in addition to a Footpath Live Load corresponding to 500 kg/m. 20 of Footpath area as per Clause 206.3 of IRC - 6 (2017). However, the present Footpath has also been designed for a wheel Load of 4 tonnes distributed over a contact area of 300 mm dia at a peak stress of 25.4 N/mm² (6.2 MPa), allowing 25% increase in stresses due to flexure.

The Contractor shall be responsible for constructing and maintaining all parts of the structure in a stable, acceptable and serviceable condition, ensuring no part under construction is unduly stressed and unsafe.

- CONSTRUCTION SEQUENCE:** Extra Deck (i.e. the Superstructure comprising the cast in situ Reinforced Concrete base (welded steel) shall preferably be constructed in one operation in one day for one span. If it is not possible, then the two spans shall be cast one after the other (each) up to about 150 mm below the top finished top one day. If possible, references on no successive days, one after the other, along with the Class Grades, in respect of the two spans on the next day. This Extra Deck must be cast in situ on girders, in respect of the two spans on the next day. This Extra Deck must be cast in situ on girders, in respect of the two spans on the next day.

CEMENT:

- A high strength Ordinary Portland Cement 53 Grade, conforming to IS: 12269 or 43 Grade conforming to IS: 8112, capable of achieving the required design concrete Strength and Durability, shall be used.
- Cement shall be obtained from approved Manufacturers only.
- Cement content in the Concrete Mix for Reinforced Concrete shall not be less than 300 kg/m³ and not more than 450 kg/m³.

COARSE AND FINE AGGREGATES:

- Maximum size of Coarse Aggregate used shall be 20mm. Fineness Modulus of Sand (fine Aggregate) shall not be less than 2.3. Both these Aggregates shall be of Approved Quality, from Approved Sources, and of Approved Gradations, etc. conforming to IS 303 (1970). In zones of congestion in the structural sections, if absolutely necessary, 12 mm down sized Coarse Aggregate may be used (but the Mix shall then be re-designed to suit).
- In zones of congestion in the structural sections, if absolutely necessary, 12 mm down sized Coarse Aggregate may be used (but the Mix shall then be re-designed to suit).

- ADDITION:** To satisfy moisture availability and increase initial setting time of concrete and cement grade, Admixtures conforming to IS: 9103, and ASTM G-494 Type I water-reducing, high range admixtures, shall be permitted in appropriate dosages, subject to their satisfactory performance.

REINFORCEMENT:


- All reinforcing steel bars shall be High Yield Strength Deformed type and Thermo Mechanically Treated, having specified minimum 5.5 per cent proof stress of 500 MPa conforming to IS: 1786.
- Minimum lap-length of reinforcement bars shall be 52d where d is the dia of the smaller bar to be lapped (unless otherwise specified).
- Not more than 50 percent of reinforcement crossing a section shall be lapped at that location.
- All laps in reinforcement shall be properly staggered and minimum distance between the laps shall be 1.3 times the lap length.
- Bending of reinforcement bars shall be as per IS 2502.

- WATER:** Water for concrete and for its curing shall be of potable quality and presence of any salts, sulphates and alkalis like chlorides, sulphates, alkalis, etc., shall be well within their limits specified in the relevant Specifications.

CONCRETE AND CURING:

- WATER-CEMENT RATIO:** by weight, shall not exceed 0.45 for Reinforced concrete.
- MINIMUM CLEAR CONCRETE COVER:** to reinforcement bars shall be 40mm.
- CONTROL OF SURFACE EVAPORATION**

SURFACE EVAPORATION FROM PLASTIC CONCRETE



Use the graphical figure below to estimate and control the loss of water through surface evaporation in the hot concrete one or more of the following actions shall be taken to reduce the surface evaporation rate to no more than one kilogram of water per square meter of surface area per hour:

- Construct Windbreaks to effectively reduce the wind velocity (to suit) in the area of concrete placement. The construction of windbreakers or enclosures should not proceed without approval of the Engineer with respect to their structural design relative to safety, stability, adverse loads, and vibrations in the long run.
- Install stationary Fog Sprayerns speed of the concreting operation to effectively increase the relative humidity in the area of concrete placement.

- When necessary, effectively reduce the temperature of concrete (to suit) by cooling one or more of its components as well as lightly spray the wet surfaces and the hot reinforcement, viz., if added to the mix-water, must be completely melted prior to using the water.

GRADATION OF CONCRETE

The structural concrete involved in this Bridge Deck shall be suitably designed as High Strength Concrete Mixes having 28 day minimum water Cube Crushing Strength in Compression on 150 mm Standard Cubes as follows:

For the cast in situ (old) Reinforced Concrete 4-Wheelbed Load Superstructure (i.e. for its Stern/Bottom, Side and Cross-girders)	35 MPa (i.e. M-30 Grade Concrete)
For the Reinforced Concrete In-Precast/Footpath Slabs, -Pavement Paving and their Bases -Road Pavement	35 MPa (i.e. M-30 Grade Concrete)

CONSTRUCTION JOINTS:

- As far as possible the location of Construction joints shall be as shown in the Drawings, but if not shown on the Drawings but absolutely necessary, they shall be planned in advance and the placing of concrete carried out continuously from joint to joint.

- A Construction Joint should not be located near the centroid level of the section as here transverse SHEAR stress is highest. The joint should be nearly perpendicular to the principal lines of tensile stress and in general be located at points of minimum shear and minimum moment - as far as possible.

- Where dowels, reinforcing bars, or other adequate ties are not shown at Construction joints in the Drawings, 'veep' should be formed of reasonable spacing by embedding water soaked burlap/binders while the concrete is still wet.
- These keys should be as deep as may be shown in the details, or as directed by the Engineer, and these key-forming binders shall be removed when the concrete has fully set.

- In resuming concreting work, the surface of the concrete previously placed shall first be thoroughly cleaned of dirt, scum, sludge, loose particles, aggregates, and any other wet material, using dry wire brushes, and, if deemed necessary, by the Engineer, to be used.

- The concrete surface shall then be thoroughly soaked with clean water (just before further concreting) and the free water, etc. as down away, and the desired concrete surface prepared with this layer of cement slurry, and only then further concrete poured.

- 'Wet-mat' and other similar items do not provide a proper construction joint, and they shall not be used.

COLD JOINTS:

- When a delayed horizontal placement of concrete in any structural member is interrupted or delayed, for any reason, for a period long enough for the previously partially placed concrete to take in initial set, the Engineer may declare such a joint as a Cold Joint and the Contractor shall immediately remove the previously partially placed concrete from the Forms.
- However, where feasible, the previously partially placed concrete may instead be suitably and carefully finished and its hatched and brought into 'low shear low moment' zone as far as possible, and given other key depressions after bringing it nearly perpendicular to the principal lines of tensile stress (for example brought to vertical or nearly vertical in a beam with principal bending moment horizontal) and thereafter some treatment shall be given to it as in a Construction Joint and only then the concreting resumed (making sure all reinforcements are as per the approved Drawings and the Shuttering has been brought to line and plumb tightly).

CURING AND PROTECTION OF YOUNG CONCRETE:

- All structural concrete shall be cured for a period of time required to obtain the specified strength, but for not less than fourteen consecutive days (ten days) beginning immediately after final setting of concrete (which is when it is set to surface stress).
- Curing (Membrane-curing or Water-curing) of cast concrete shall be carried out as generally explained below:

Membrane-Curing the Concrete:

- Except for at Construction Joints and surfaces sealed by Forms, liquid membrane-curing compound can be used for curing the concrete as follows:
- On bridge deck top surface and other exposed surfaces, liquid membrane curing compound shall be applied once after initial setting and as the Surface Sheen has disappeared and the concrete is still slightly damp (not wet).
- On structural (i.e. formed vertical) surfaces, Forms shall be stripped as soon as practical (generally after 24 hours of casting) and liquid membrane curing compound applied immediately except in the areas that require rubbing or finishing during the curing period.
- These areas shall be kept water-wet until their finishing is completed, where after the liquid curing membrane shall be uniformly applied on them also when their surface is damp.
- White pigmented liquid membrane curing compound shall be used for all surfaces where the structure temperature during curing period is likely to reach about 25°C or more.

- For bridge decks which are to receive an asphaltic overlay, residual curing membrane (after curing) shall be removed prior to the overlaying.
- Removal methods and results should be approved by the Engineer.
- The membrane curing compound used shall be of longer lasting duration and in accordance with the requirements specified for curing membrane material, AASHTO M 148 or the equivalent Specification.

- The curing membrane shall be applied in two applications one immediately following the other.
- The rate of each application of curing compound shall be as prescribed by the manufacturer, with a spreading rate per application of at least one liter of liquid per flat square meter of concrete surface.

- If the concrete has dried up or has become dry, it shall be thoroughly wetted with water and the curing compound applied just as the surface film of water disappears and the surface is damp.

- During curing operations any unexposed surfaces shall be kept cured with wetted hessian cloth, and sprayed with the curing compound when Surface is damp not dry.

- Any curing membrane material on Construction Joints and/or on reinforcing steel shall be completely removed before the following concrete pour.
- Hand operated spraying equipment shall be capable of applying concrete and urethane pressure to provide uniform and even distribution of the curing membrane at the sites required.

- The curing compound shall be kept thoroughly mixed at all times during usage / application.
- No traffic of any kind shall be permitted on the curing membrane until the curing period is completed, design permitting.

Water-Curing the Concrete:

- All concrete surfaces, unless still covered by unbroken Forms (which shall be kept from wetting-up under ambient temperature) or submerged, shall be water-cured using liquid membrane cure.
- Water curing shall begin just after initial setting of concrete (which generally occurs by about 10 minutes of placement of concrete) and shall be continued for about 140 to 180 minutes of placement of concrete (concrete) and just after the surface water sheen has disappeared.

- Surface water-cured shall be covered with wet sand, cotton mats, or duco-thickness butyl (adhesive) sheets.
- This hessian material shall be placed tightly around and behind any projecting reinforcing steel in order to completely cover the fresh concrete surface.

- The Hessian material shall be completely saturated with water and kept continuously saturated throughout the curing period.
- After the initial saturation, water used for wet keeping, all surfaces shall be covered with thick polyethylene sheeting or other approved impervious material in order to protect/prevent drying-up of concrete surface being cure continuously.
- The sheeting shall be weighted down or secured well to prevent moisture loss but the surfaces of the concrete shall be readily available for inspection of the Engineer (or his Representative).
- The sheeting material shall be in good repair.
- Sheeting that contains holes or is otherwise damaged shall be repaired or replaced immediately.
- The Contractor shall be responsible for thoroughly inspecting and monitoring the concrete surfaces throughout the curing period to ensure continuous and curing.
- Additional water shall be provided any areas where saturation is reduced.
- Operation of curing by the Contractor shall be conducted at least TEN times per day and night for the duration of the curing period - and even more often if ordered so by the Engineer.
- The Engineer shall be advised if the curing inspection schedule and his (or his Representative) may accompany the workmen to verify the acceptability of curing.

COLD-WEATHER CURING:

- When concrete is placed and its air temperature is expected to drop below 5°C during the curing period, the Contractor shall provide suitable measures such as straw, additional burlap or other suitable insulating materials and/or housing and artificial heat-curing to maintain the concrete temperature between 10°C and 32°C as measured on the surface of the concrete.
- The surface of the concrete shall be kept moist and warm by the use of an approved moisture barrier such as wet hessian and Butyl Sheetings.
- The moisture barrier should be maintained in intimate surface contact with the concrete during the entire curing period.
- After the completion of the curing during the entire required curing period, the Contractor shall stop the curing and remove the protection in such a manner that light curing of the concrete will be provided.
- When concrete is placed in 'unfavourable' and subsequently flooded with ground water, the above curing requirements may be waived, provided the surface of the water is not permitted to freeze.

'CONCRETING' IN 'ADVERSE WEATHER' CONDITIONS:

1. 'Concreting' in 'Cold' Weather:

- Concrete that freezes soon after placing, gains rather low strength and some permanent damage is liable to occur. Therefore, such concrete shall be removed and replaced immediately.
- Planning for Protection of fresh concrete during placement, and until it has attained the minimum properties required for the environment and the loading to which it will be applied, shall be done well in advance of concreting and approved by the Engineer.
- Appropriate equipment shall be made available in time for heating the concrete materials, for constructing enclosures and for maintaining favourable temperatures even after the concrete is placed.
- Concrete shall never be placed in cold Forms and cold steel.
- When the temperatures of the mixes is below 5°C, the Contractor shall use means to raise their temperatures to above 10°C.
- When faced with prolonged cold temperatures, at aggregates, or mixing water, or both, shall be heated to about 25°C to 32°C.
- At temperatures at least 10°C above freezing, it is seldom necessary to heat the Aggregates.
- At temperatures below or at freezing, often only the Fine Aggregate is heated to produce concrete of the required temperature, provided the Coarse Aggregate is free of frozen lumps and the Temperature of Water for the Mix is at least 10°C.
- If aggregate temperatures are above freezing, the desired concrete temperature usually can be obtained by heating only the mixing water.

CONTINUE

GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF HIGHWAYS BRIDGE BRANCH	
STANDARD SUBSTRUCTURE DRAWING FOR ROAD BRIDGES Road Concrete Width: 6.0m with 1 Footpath each 1.25m wide	Overall Deck Width: 8.50 m
Effective Simply Supported Span (Centre to Centre of Bearings): 20 m Reinforced Concrete Deck	LIVE LOAD: IRC Class A or 75R or 1 or 2 Lanes of Class A and Highway permits, and Footpath Loading
Dep. No.: 17 of 3-Webbed RC-Slab Deck 25.0 m x 8.50 m	
Dep. TITLE: REFERENCE NOTES (1 Sheet) of Sheet 12	
Reviewed by: Praduman Koirala (Engineer, Civil)	Forwarded by: Jyoti Mishra (S.D. Civil)
Approved by: Dipak Shrestha (E.O. DPM)	Approved by: Anshu Kumar Thapa (S.D. Civil)
Date: 20/06/2021	

- l) Appreciable fluctuation in the mixing water temperature from batch to batch shall not be allowed.

II. CONCRETING IN HOT WEATHER:

a) No concrete shall be placed when the ambient air temperature at site, site in shade is expected to exceed above 32°C during the placement process.

b) When the temperature of the concrete mixture is expected to exceed about 32°C, a retarding admixture shall be included in the approved mix design since setting time tends to reduce at higher temperatures.

c) The temperature of the concrete mixture immediately before placement shall not exceed 32°C.

d) When the ambient air temperature is above 32°C, all Forms, reinforcing steel, and other contact surfaces shall be cooled to below 32°C until concrete is placed.

e) When such high ambient temperature conditions exist, the most appropriate solution is to resort to evening out a morning time placement.

f) However, if the above stated precautions are taken to help lower the temperature of concrete surface and the concrete mix ingredients are also cooled (immediately), concreting can be carried out even during day hours provided the ambient air temperature in shade does not exceed 40°C.

g) Movers, chutes, hoppers, pump-line, and other production and placement equipment can be braked.

h) Paved area, covered with two layers, or otherwise coated to reduce the effect of the sun's heat.

i) Forms and reinforcing steel can be sprinkled with cold water and covered with wet burlap until concrete reinforcing commences.

j) Sprinkling the area with water sprays, carefully coats the contact surfaces and surrounding area and thereby increases its relative humidity.

k) This not only reduces the temperature rate of the concrete but also minimizes evaporation of water from the concrete during placement and after casting.

l) For states on ground, it is a good practice to dampen the sub-grade the evening before concreting.

m) There should be no standing water or puddles on the sub-grade or inside the Forms when the concrete is placed.

n) The mix water may be cooled by using chafed or crushed ice but only as much ice should be used as will be needed immediately before the water is added to the mix.

o) All water used for making up and for cooling or sprinkling, and curing, must meet the same quality requirements as those for water used for Making of Concrete.

p) Of particular concern are the following substances and chemicals found in the mix, which can adversely affect the cement and concrete the reinforcing steel, respectively. These must be kept below their specified limits.

q) Aggregates should be cooled by shading and sprinkling water (top spray).

r) Transporting and placing concrete should be done as quickly as practical during hot weather.

s) Delays contribute to loss of slump, a damaging increase in concrete temperature and loss of workability.

t) Enough workmen and equipment shall always be available to handle and place concrete immediately upon delivery.

u) Prolonged mixing even at signaling speed of the Drum, shall be avoided since it might heat up the mix and reduce workability.

v) If delay occurs, the heat generated by continued mixing/lighting can be removed by spraying the mixer and then agitating immediately, but the delays should be kept to a minimum.

w) In hot concrete haulers never rapidly in hot weather. extra care in the above techniques is required to avoid Code 200.

x) For placement of concrete in Walls, Shafts, Columns, etc. shrouding layers may be required to assure proper curing and reinforcement and must be used with strict, effective disposition of heat of hydration and to prevent segregation of the mix.

y) Temporary curbsides and windbreakers help to minimize adverse effects of hot weather, winds, and surface evaporation.

CAUTION AGAINST "PLASTIC SHRINKAGE" CRACKING OF Concrete AND USING EXCESSIVE DOSAGES OF ADMIXTURES like "RETARDER" and "SUPER - PLASTICIZER"

a) Plastic Shrinkage cracks develop prior to initial setting of concrete and can appear many months later in service. If the rate of initial setting from the freshly laid concrete is faster than the rate of initial setting from the concrete surface, the concrete tends to dry, hence, shrink, causing cracks in plastic concrete due to tension from the shrinking under such conditions. These cracks trend downwards from the surface and tend to propagate at an angle of 45° to the vertical.

b) The longer the initial setting time, deeper will these cracks penetrate. Should they travel down to a sufficient depth of slab, then the slab can become a batch of isolated concrete slabs separated by cracks and hence not be structurally monolithic with the rest of the slab-section. Such deep-seated cracks are difficult to detect, generally it is not possible to detect the extent of these cracks. The result may be a major Damage, requiring major rehabilitation.

c) Hence minimum doses of Retarders and Super-Plasticizers shall be used so as to keep the initial setting time to just the required minimum to allow the required workability of concrete.

d) These cracks can be of random pattern (polygonal/cracks) and/or may be somewhat parallel to each other and nearly perpendicular to the direction of wind that prevailed at the time of casting. Hence the field staff must look for these cracks before the concrete has fully set and, should these cracks occur, the plastic concrete should be quickly lightly re-worked on its surface (not re-troweled to close these cracks in time).

e) Concrete slabs which are correctly re-worked should not exhibit Plastic Shrinkage cracks because the action of reworking is a form of re-compaction that tends to close any voids in the concrete. (This reworking can, however, aggravate sedimentation of aggregates in the mix and cause Plastic Settlement cracks - see above).

f) Although the Plastic Shrinkage cracks can be wide at their start (even up to 2 mm), the wide rapidly diminishes with depth. Nevertheless, if severe cracks may also pass through the full depth of a slab, in contrast with most types of Plastic Settlement cracks, it is not noticed in the depth of re-worked aggregate-slab-sections, though setting at the top of the slab may show them in case of full depth penetration. Taking care can reveal them precisely.

g) Plastic Shrinkage cracks rarely follow the free ends of the slab (i.e. the edges of a slab) because these edges are free to move under plastic shrinkage. This is a very important aspect differentiating them from long-term drying shrinkage cracks. If the time of formation is unknown, however, Plastic Shrinkage cracks will turn up to the ends of a slab which has been cast against a previous pour, especially if there is continuity of steel, because this steel is re-entrant.

h) The factors that determine rate of surface evaporation are the temperature of the concrete, the temperature, relative humidity, and wind velocity of the air adjacent to the concrete. The evaporation increases as the humidity decreases, as the wind velocity increases, as the air temperature decreases, and as the concrete temperature increases. Of particular interest, is the fact that rapid evaporation is at least as big a problem in cold weather as in hot weather. Even when the relative humidity is 100% per cent in cold weather, there will be a large amount of evaporation if the concrete is warm. All of the factors listed above, only the concrete temperature is easily controllable. There is a definite advantage to cool the concrete, it should be placed as cool as possible in warm weather, and should not be over-heated in cold weather. If the concrete temperature is reduced to about 20°C to 15°C, much of the evaporation can be eliminated.

i) In hot weather, sometimes concreting during 4 p.m. on the previous day to 12 noon on the next day may be resorted to for preventing formation of Plastic pour cracks obtaining better quality concrete. But this will be effective only if it gives significantly lower concrete temperature and lower wind velocity. The reduction of air temperature BUT NOT that of concrete temperature with the increase in relative humidity will not significantly reduce the Plastic Shrinkage cracking.

j) If it is not possible to eliminate the risk of Plastic Shrinkage cracks even by improved early curing, then reduction to the concrete mix must be considered. First, check that the concrete mix is in agreement with high moisture effects. If it does, try to reduce it or replace it with one that does not retard so much (rather than use it by adding a compensating accelerator). Second, consider the use of an entrainment. Air-entrained concrete exhibits less Plastic Shrinkage cracks than plain concrete. This is due to the entrainment of air in the concrete. If an entrainment is used, the rate of bleeding it should increase the risk of Plastic Shrinkage cracking occurring at a given rate of evaporation. However, most commercially available air-entraining agents are deleterious and therefore reduce the surface tension caused by drying, and consequently reduce the shrinkage-cracking.

k) The prevention and timely repair of Plastic Shrinkage cracks in slabs is particularly critical. This is because the cracks are wide at the top and can rapidly take in pollutants which may cause subsequent scaling and prevent the subsequent satisfactory application of sealing materials. Clearly water cracks in slabs are not likely to be "self-healing" at the top and are likely to spread and allow ingress of pollutants.

CAUTION AGAINST POSSIBLE DAMAGE DUE TO "PLASTIC SETTLEMENT" CRACKING OF CONCRETE

a) Plastic Settlement cracks occur in non-instantly-set concrete when there is a relatively high amount of swelling through it and some form of obstruction to the downward sedimentation of the solids (i.e. the reinforcement bars). These obstructions break the back of the setting concrete over them as its solids fall downwards around them, forming formation of hollows under their belly. Thus Cracks show directly over the hollows or voids and over reinforcement near the top surface of the concrete, reflecting their pattern. Such Cracks can also occur in narrow columns and walls where steel sedimentation is prevented by the resulting rigidity of the concrete due to downward passage for sedimentation and there may be further aggravation by the presence of horizontal bars.

b) Plastic Settlement Cracks can be prevented by reducing the bleeding and hence the sedimentation, and by reducing the obstructions to sedimentation.

c) Admixtures such as plasticizers, retards, water repellents and those that are most effective, such as retarders, plasticizers, and sedimentation and hence the plastic settlement cracks. These can also be minimized by light re-troweling (or re-working) of the not-yet-finally-set concrete if they have formed, thus also filling back the under belly hollows.

d) This light re-trowelling should not be applied too soon otherwise a second phase of bleeding can still cause Plastic Settlement cracks. The correct time as well as being determined by simple site tests it will be the last time that a vibrating pour can be inserted into the concrete and removed without leaving a significant scale. Re-trowelling is often the only way to eliminate plastic settlement cracks, particularly in deep sections. "Trowelling the surface can actually aggravate these cracks as the pressure may only cause further settlement of solids.

REMARKS OF CRACKS DUE TO "PLASTIC-SHRINKAGE" AND "PLASTIC SETTLEMENT" IN CONCRETE WHILE IT IS STILL PLASTIC AND HAS NOT YET ATTAINED "INITIAL SET"

a) Plastic cracks by their very nature pass through the cement matrix and good aggregate particles, therefore they are very jagged and capable of inflicting shear, providing there is sufficient reinforcement to maintain aggregate integrity. Consequently full structural repairs (i.e. repair formulations) may not be necessary - though "pre-tensioning" BUT only if the crack penetration is minor. REPAIRS otherwise if deep penetration damage is done, EPORING will NOT restore full monolithic (in which case the Deck slab may have to be demolished, reworking, repair, and very costly rehabilitation operation). HENCE REMARKS OF PLASTIC CRACKING.

b) If cracks follow the pattern of the steel reinforcement it may be difficult at first to determine whether they are due to Plastic Shrinkage or Plastic Settlement. It can be shown that the cracks "pass through" the steel and follow the pattern of the steel, then they are almost certainly Plastic Shrinkage cracks that have been created by the steel!

c) Plastic cracks often form on the top face of sections e.g., Plastic Shrinkage cracks in slabs, and/or Plastic Settlement cracks on top of deep beams and walls. They may be associated with plastic shrinkage, plastic settlement, or both. Plastic cracks means that they may not be as thermal contraction and drying shrinkage take place. Consequently it may be wise to fill plastic cracks with "light epoxy materials" until it is certain that the long-term effects have subsided.

d) Plastic Settlement cracks occur under steel and are typically sealed. If the concrete is in an exposed state, to eliminate the risk of corrosion of the steel, reduced bond strengths due to under belly voids thus formed under steel bars are dangerous.

ACCEPTABLE CRITERIA OF CONCRETE CURING TEST RESULTS FOR THE STAGING SUPPORTING THE DECK IN A SPAN AFTER SUCCESSFULLY CURING THE CONCRETE IN THE DECK

a) The acceptability criteria of Standard Code curing test results shall be not more than 5% of works cubes fall below the specified minimum work strength. For the 10% to be fulfilled, the Mean Strength of works cubes tested at 28 days against 1.64 times the "Standard Deviation" should not be less than the required minimum 28 days work strength.

b) ALTERNATIVELY if the Standard Deviation for the concerned Concrete has not been established, the cube strength shall be accepted as complying with the strength requirement, if "none of the specimens tested falls below the minimum specified strength" or "if the average strength of the specimens is at least the specified strength, i.e. individual test, mean, standard deviation, etc. of the minimum required work strength and the difference between the maximum and the minimum strengths of the test specimens is NOT GREATER THAN 20% of that strength."

c) In case of a dispute about the strength of concrete in a particular area of the cast concrete, three 10 mm dia. and 100 mm long Standard concrete cube shall be drilled out from such an individual area and tested for their crushing compressive strength. These values shall be neither for concrete age and how the concrete were cast, and the corresponding equivalent "cube" strengths worked out to each core. If their average exceeds 85% of required 28 days work strength and one falls below 75% of the required 28 days work strength, then concrete strength in such drilled area may be accepted, BUT of course subject to contractual conditions for poor work.

d) RELEASE OF THE STAGING SUPPORTING THE DECK IN A SPAN AFTER SUCCESSFULLY CURING THE CONCRETE IN THE DECK as specified above and the concrete in it attains a minimum work Cube Crushing Strength of 280 kg/cm². Age of Concrete approximately 21 days after casting the staging supporting the Deck may be released. The specimens (i.e. the Deck) shall not be loaded until after its concrete is at least 28 days old and crushing cube strength of its concrete is 280 kg/cm².

BEARINGS

a) NEOPRENE BEARINGS shall be used. Their Material specifications, Design, Acceptance Criteria and Installation shall be generally in accordance with IS 803 part 1 (2015), the AASHTO Design Specifications, and Sound Engineering Practice.

b) The Bearings shall be obtained from approved and experienced Manufacturers.

c) Installation of Bearings shall be carried out under the expert supervision of the Manufacturer's Technical Representative.

d) The Design of Bearings shall be based on the Design Loads, Relations, etc., given in the appropriate Table in the attached relevant Drawing.

e) Detailed Drawings shall be prepared by the Manufacturer, which shall be checked and duly approved before the Bearings are manufactured and installed.

f) Neoprene Bearings shall be bonded to their R.C. pedestal by appropriate Epoxy Adhesive. The Grout/bedding Mortar when used, shall be high strength fast setting Non Shrink Type.

g) All Bearings shall be placed in truly horizontal plane only and to true line and direction (unless shown differently; as generally indicated in the attached relevant Drawing).

h) In case of the contractor's failure to change the type of Bearings from Neoprene to POT Bearings (POT Filled and POT-PTFE Filled), then the magnitudes of Vertical loads, Horizontal loads and movements, etc. tabulated in Dtg. No. 017 of 3-Mileover RC Deck Deck 25.0 m SS Span will all change and the same will then have to be re-worked out and the design of POT Bearings done accordingly. The Substructure and Foundations shall then be designed according to the correctly re-worked out Loads, Forces and Movements, etc.

17. EXPANSION-CONTRACTION JOINTS

a) These Movement Joints shall be provided in the deck as Specified and shown in attached relevant Drawing. There shall be of Approved Quality and shall be fixed under the expert supervision of the Manufacturer at the appropriate ambient temperature as per design.

b) An other type of expansion joint like compression seal, slab seal, etc. that satisfies the requirement as shown in relevant drawing can also be used under the supervision of concerned Engineer.

18. WEARING COURSE: Asphaltic concrete / Premix wearing COURSE, 75mm thick at roadway crown, gradually increasing to 50mm at the road Kinks, shall be provided over the Deck Slab.

19. EARTHQUAKE EFFECTS: The Horizontal Seismic coefficient assumed is 0.18 (i.e. 0.16Q as prescribed by a Vertical Seismic coefficient of 0.7 or 0.12Q).

20. DESIGN CONSULTANT: Research for National Development center (P) Ltd. Lalpur, Bahawalpur.

LIST OF DRAWINGS:

DRAWING TITLE	REFERENCE NOTES (2 Sheets)	Sheet 12
REFERENCE NOTES (2 Sheets)	Sheet 22	
SUPERS ELEVATION, OUTLINE & DIMENSIONS		
REINFORCEMENT DETAILS OF DECK SLAB FOOTPATH SLAB, ROAD KERB & PARAPET POST		
REINFORCEMENT DETAILS OF LONGITUDINAL GIRDERS		
REINFORCEMENT DETAILS OF CROSS GIRDERS & MISCELLANEOUS DETAILS		
BAR BENDING SCHEDULE		
1 of 3 Mileover RC Deck Deck 25.0 m SS Span		
2 of 3 Mileover RC Deck Deck 25.0 m SS Span		
3 of 3 Mileover RC Deck Deck 25.0 m SS Span		
4 of 3 Mileover RC Deck Deck 25.0 m SS Span		
5 of 3 Mileover RC Deck Deck 25.0 m SS Span		
6 of 3 Mileover RC Deck Deck 25.0 m SS Span		
7 of 3 Mileover RC Deck Deck 25.0 m SS Span		

GOVERNMENT OF PUNJAB
MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT
DEPARTMENT OF ROADS
BRIDE BRIDGE

STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGES

Standard Superstructure Drawing for Road Bridges
Effective Span Width 12 m
Effective Span Width 12 m
Effective Span Width 12 m

Effective Span Width 12 m
Effective Span Width 12 m
Effective Span Width 12 m

Effective Span Width 12 m
Effective Span Width 12 m
Effective Span Width 12 m


Effective Span Width 12 m
Effective Span Width 12 m
Effective Span Width 12 m

Effective Span Width 12 m
Effective Span Width 12 m
Effective Span Width 12 m

Effective Span Width 12 m
Effective Span Width 12 m
Effective Span Width 12 m



Effective Span Width 12 m
Effective Span Width 12 m
Effective Span Width 12 m

Effective Span Width 12 m
Effective Span Width 12 m
Effective Span Width 12 m




NOTES:


1. EXACT QUANTITIES SHALL BE CALCULATED BY THE CONCERNED ENGINEER FOR COSTING PURPOSES.
2. TOTAL WEIGHT OF ENTIRE SUPERSTRUCTURE IN ONE SPAN = 333 Tonnes.
3. CONCRETE TILES CAN BE REPLACED WITH M20 CONCRETE IN REMOTE AREAS.




 GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL, INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS BHICTE (MINISTRY)	
STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGE	
Bridge Configuration: Width: 6.3m with 2 Footpaths each 1.00m wide Effective Span: Single Spanned Spans: 2 spans of 20m, 2.0 m Substructure: Concrete Deck (on RCIS)	Overall Deck Width: 8.30 m LINE LOAD: RC Deck of 75mm or 1.0 m 1.0m of Chalk & 1.0m of concrete, and Footpath Loading
Draw. No: 37 of 3-Whibbled RC-Slab Deck 25.0 m-Span Draw. TITLE: SUPERSTRUCTURE OUTLINE AND DIMENSIONS	
Reviewed by: Project Manager (Engineer: GOR) Recommendation by: Circle Office (Engineer: GOR)	Approved by: Assistant Engineer (SDE: Civil) Approved by: Chief Engineer (SDE: Civil)
Signature: _____	Date: June 2021 Revision: _____




REINFORCEMENT DETAILS OF DECK - PLAN VIEW
SCALE - 1 : 100 @ A3 PAPER




REINFORCEMENT DETAILS OF DECK - SECTIONAL VIEW (SEC 4 - 4)
SCALE - 1 : 50 @ A3 PAPER




REINFORCEMENT DETAILS OF PARAPET POST - SECTIONAL VIEW
SCALE - 1 : 25 @ A3 PAPER




REINFORCEMENT DETAILS OF ROAD KERB - SECTIONAL VIEW
SCALE - 1 : 25 @ A3 PAPER




SECTIONAL VIEW OF POST (SEC 5-5)
SCALE - 1 : 50 @ A3 PAPER



ELEVATION VIEW OF PARAPET POST
SCALE - 1 : 50 @ A3 PAPER




HALF SECTIONAL PLAN VIEW OF PRECAST R.C. FOOTPATH SLAB
SCALE - 1 : 50 @ A3 PAPER




SECTIONAL DETAIL (SEC 7-7)
SCALE - 1 : 50 @ A3 PAPER

Concrete Terra Slope Pavement
400/450/500mm (URBAN AREA) OR
M15 / 50 mm Thick Concrete Flooring
(SMOOTHING FOOTPATH SURFACE)



SECTIONAL REINFORCEMENT DETAILS OF PARAPET POST (SEC 6-6)
SCALE - 1 : 20 @ A3 PAPER




SECTIONAL DETAIL (SEC 8-8)
SCALE - 1 : 50 @ A3 PAPER

NOTE:

- Concrete flooring tiles on footpaths in urban area and bituminous approach road. In other region 50 mm thick M20 Concrete flooring above concrete precast slab can be provided for smooth surface in footpaths.
- Maximum width of footpath slab is 1.0m and footpath slab shall be of appropriate size.


GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS BIRATNAR	
STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGES	Overall Deck Width: 4.0m with 2 Footpaths each 1.2m wide
Road Configuration: W 4.0m with 2 Footpaths each 1.2m wide (Effective Simply Supported Span (Center to center of Bearings) 20.0m Reinforced Concrete Deck (100mm)	LIVE LOAD: IRC 1 Lane of 70k or 1 or 2 Lanes of Class A, whichever governs, and Footpath Loading
Drp. No.: 47 of 3-Whiskered RC-Deck 25.0 m x 5.0 Span	
REINFORCEMENT DETAILS OF DECK SLAB, FOOTPATH SLAB, ROAD KERB & PARAPET POST	DATE: JUNE 2021
Reviewed by: Pradip Kumar (Engineer, Draft)	Prepared by: Jyoti Malla (Engineer, Draft)
Recommended by: Chandra Shekhar (E.O.G., Draft)	Approved by: Jyoti Malla (E.O.G., Draft)




REINFORCEMENT DETAILS OF EXTERNAL MAIN GIRDER - LONGITUDINAL HALF SECTIONAL VIEW
SCALE: 1:100 @ A3 PAPER




EXTERNAL MAIN GIRDER BAR ARRANGEMENT DETAIL (DETAIL AT C)
SCALE: 1:10 @ A3 PAPER




SECTIONAL DETAIL (SEC 10-10)
SCALE: 1:50 @ A3 PAPER




SECTIONAL DETAIL (SEC 11-11)
SCALE: 1:50 @ A3 PAPER




SECTIONAL DETAIL (SEC 12-12)
SCALE: 1:50 @ A3 PAPER




SECTIONAL DETAIL (SEC 13-13)
SCALE: 1:50 @ A3 PAPER




SECTIONAL DETAIL (SEC 14-14)
SCALE: 1:50 @ A3 PAPER




REINFORCEMENT DETAILS OF INTERIOR MAIN GIRDER - LONGITUDINAL HALF SECTIONAL VIEW
SCALE: 1:100 @ A3 PAPER




INTERIOR MAIN GIRDER BAR ARRANGEMENT DETAIL (DETAIL AT D)
SCALE: 1:10 @ A3 PAPER




SECTIONAL DETAIL (SEC 15-15)
SCALE: 1:50 @ A3 PAPER



SECTIONAL DETAIL (SEC 16-16)
SCALE: 1:50 @ A3 PAPER




SECTIONAL DETAIL (SEC 17-17)
SCALE: 1:50 @ A3 PAPER




SECTIONAL DETAIL (SEC 18-18)
SCALE: 1:50 @ A3 PAPER


GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS BRIDGE DIVISION			
STANDARD REINFORCEMENT DRAWINGS FOR ROAD BRIDGES			
Road Construction with 3.0m or more width with 3.0m or more width	General Deck Width: 3.0m		
Effective Simply Supported Span (center to center of bearings) 2.0m Reinforced Concrete Deck with and Reinforced Concrete	LIVE LOAD: IRC 1 Lane of 75kN or 1 or 2 Lanes of Class A, whichever governs, and Footpath Loading		
Dwg. No.: 37 of 3-Webbed RC-Deck 25.0 m-Span			
REINFORCEMENT DETAILS OF LONGITUDINAL GIRDER			
Reviewed by Pradip Kumar (Engineer, DoP)	Prepared by Jyoti Malla (SCE, DoP)	Checked by Jyoti Malla (SCE, DoP)	Date June 2021
Recommended by Gyanendra (DO, DoP)	Approved by Gyanendra (DO, DoP)	Approved by Gyanendra (DO, DoP)	00




REINFORCEMENT DETAILS OF MID CROSS GIRDER - LONGITUDINAL HALF SECTIONAL VIEW
SCALE - 1:100 @ A3 PAPER




REINFORCEMENT DETAILS OF END CROSS GIRDER - LONGITUDINAL HALF SECTIONAL VIEW
SCALE - 1:100 @ A3 PAPER




SECTIONAL DETAIL (SEC 19-19)
SCALE - 1:50 @ A3 PAPER




ISOMETRIC DETAIL VIEW OF EXPANSION JOINTS DETAILS AT ABUTMENT
SCALE - NON




DETAIL OF MESH (BAR-EC5)
SCALE - 1:50 @ A3 PAPER




SECTIONAL DETAIL (SEC 20-20)
SCALE - 1:50 @ A3 PAPER



EXPANSION JOINTS DETAILS AT ABUTMENT
SCALE - 1:40 @ A3 PAPER



INSTALLATION OF BEARINGS WHEN SUPERSTRUCTURE IS AT GRADE
SCALE - 1:100 @ A3 PAPER



EXPANSION JOINTS ARRANGEMENT IN A CARRIAGEWAY
SCALE - 1:10 @ A3 PAPER



DRAINAGE SPOUT DETAIL
SCALE - 1:40 @ A3 PAPER



LONGITUDINAL CAMBER PROFILE TO BE GIVEN TO SOFFIT OF DECK
SCALE - NON

Load Condition	Data for Substructure and Foundation Design			Remarks
	Right Exterior Girder	Inner Girder 1	Left Exterior Girder	
Dead Load (Slab and Girder)	388.71	432.73	388.71	
SIDL, Wearing Course	26.13	56.25	26.13	
SIDL, Railing and Utilities	109.78	Negligible	109.78	
Pedestrian Load	51.78	Negligible	51.78	
2 Lane of IRC Class A	250.72	257.15	263.58	Excluding I.F.
IRC Class 70 R (Tracked)	249.11	212.01	174.91	Excluding I.F.
IRC Class 70 R (Wheel)	318.68	265.02	211.36	Excluding I.F.

DATA FOR BEARINGS		
Load Condition	Area	On each Abutment Bearing
Under Maximum Live Load	IV	962 kN
	V	137 + 42 kN
	VI	187 kN
	III	0.001322/Reaction
	II	12 mm

NOTES:		
"N"	Vertical Load	
"H"	Longitudinal Horizontal Force	
"T"	Transverse Horizontal Force	
"R"	Rotation About Bridge Transverse Axis	
"L"	Longitudinal Movement for Design Purpose	
"S"	Shear Rating of Bearing	

GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS BRIDGE DIVISION		
STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGES		
Road Carriageway Width: 6.0m with 1 Footpath each 1.25m wide	Overall Deck Width: 8.50 m	
Effective Simply Supported Span (center to center of Bearings): 30.0 m and Footpath Loading	LIVE LOAD: IRC 1 Lane of 75R or 1 2 Lane of Class A, whichever governs, and Footpath Loading	
Dwg. No.: 47 of 3-Webbed RC-Slab-Deck 23.0 m-SS Span		
REINFORCEMENT DETAILS OF CROSS GIRDER & MISCELLANEOUS DETAILS		
Prepared by: Pradip Kumar (Engineer, Civil)	Forwarded by: Jyotiendra Mishra (S.D.O., Civil)	Date: June, 2021
Recommended by: Chandra Shekhar (D.O., Civil)	Approved by: Anil Kumar (S.D.O., Civil)	Remarks: 00

BAR BENDING SCHEDULE OF EXTERIOR MAIN GIRDER (1NO)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	EMG 1		32	26220	10	262.20	1655.27
2	EMG 2		32	24050	4	96.20	607.21
3	EMG 3		32	17800	4	71.20	446.49
4	EMG 4		32	11550	2	23.10	146.83
5	EMG 5		32	8425	2	16.85	106.37
6	EMG 6		20	26220	4	104.88	256.53
7	EMG 7		10	25420	12	305.04	198.21
8	EMG 8		12	7880	149	1174.12	1042.52
9	EMG 9		32	245	128	31.36	197.98
Total Weight (KG)						4801.71	

BAR BENDING SCHEDULE OF INTERIOR MAIN GIRDER (1NO)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	IMG 1		32	26220	10	262.20	1655.27
2	IMG 2		32	17800	4	71.20	446.49
3	IMG 3		32	11550	2	23.10	146.83
4	IMG 4		32	8425	2	16.85	106.37
5	IMG 5		20	26220	4	104.88	256.53
6	IMG 6		10	25420	12	305.04	198.21
7	IMG 7		12	7880	149	1174.12	1042.52
8	IMG 8		32	245	102	24.90	157.76
Total Weight (KG)						4150.01	

BAR BENDING SCHEDULE OF DECK SLAB (1NO)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	S1		12	8620	256	2206.72	1099.57
2	S2		12	8620	256	2206.72	1099.57
3	S3		12	25420	56	1403.52	1219.53
4	S4		12	25420	56	1403.52	1219.53
5	S5		12	1700	387	657.50	594.27
Total Weight (KG)						7142.41	

BAR BENDING SCHEDULE OF MID CROSS GIRDER (1NO)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	MC1		20	6670	6	36.42	97.21
2	MC2		20	6670	4	26.28	54.81
3	MC3		10	2880	32	91.20	56.27
4	MC4		10	6270	6	36.42	30.95
5	MC5		20	220	12	2.64	1.63
Total Weight (KG)						255.85	

BAR BENDING SCHEDULE OF END CROSS GIRDER (1NO)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	EC1		20	6670	6	36.42	97.21
2	EC2		20	6670	6	36.42	97.21
3	EC3		10	2880	32	91.20	56.27
4	EC4		10	6270	6	36.42	30.95
5	EC5		20	220	12	2.64	1.63
6	EC6		10	1000	2	3.20	1.97
Total Weight (KG)						290.12	

BAR BENDING SCHEDULE OF PARAPET POST BASE (1 SIDE)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	MB1		10	1470	120	248.40	154.19
2	MB2		10	25420	6	152.52	94.10
BAR BENDING SCHEDULE OF RAILING POST (1 SIDE = 14Nos)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
3	MR3		16	2196	96	122.92	186.07
4	MR4		6	960	96	94.88	21.88
Total Weight (KG)						465.04	

BAR BENDING SCHEDULE OF ROAD KERB (1 SIDE)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	MS1		10	1650	170	280.50	173.07
2	MS2		10	25420	6	152.52	94.10
Total Weight (KG)						267.17	

BAR BENDING SCHEDULE OF FOOTPATH PRE CAST LAB (1NO)							
S.No.	Bar Mark	Shape of Bar (Not to scale) Dimensions are in mm	Dia. of Bar (mm)	Length of each Bar (mm)	No. of Bars	Total Length of Bars (m)	Weight (kg)
1	MS1		8	710	9	6.39	2.52
2	MS2		8	100	7	0.44	2.54
3	MS3		10	710	9	6.39	3.94
4	MS4		10	500	7	4.44	3.97
Total Weight (KG)						12.98	

GOVERNMENT OF NEPAL MINISTRY OF PHYSICAL INFRASTRUCTURE AND TRANSPORT DEPARTMENT OF ROADS BRIDGE DIVISION		
STANDARD SUPERSTRUCTURE DRAWING FOR ROAD BRIDGES		
Road Cross-section: WB-4.5m with 3 Footpaths each 1.5m wide	Overall Deck Width: 9.50 m	
Effective Simply Supported Span (center to center of bearings): 20.0 m Reinforced Concrete Deck (per 3000)	LIVE LOAD: IRC 1 Lane of 75K or 1 or 2 Lane of Class A, whichever governs, and Footpath Loading	
Drg. No.: 77 of 3-Wheeled RC-Slab-Deck 25.0 m-88 Span		
BAR BENDING SCHEDULE		
Reviewed by: Pradyumn Poudel (Engineer, Draft)	Prepared by: Jyoti Poudel (JCE, Draft)	Date: June 2021
Recommended by: Gopal Shrestha (DOO, Draft)	Approved by: Anjan Kumar Thapa (DOO, Draft)	Rechecked by: Anjan Kumar Thapa (DOO, Draft)